											EOE	21.1.2	
STATE OF UTAH  DEPARTMENT OF NATURAL RESOURCES  DIVISION OF OIL, GAS AND MINING										AMEND	FOR ED REPOR	RM 3	
	APPLICATION FOR PERMIT TO DRILL									JMBER Thorne 3	-31B4		
2. TYPE C	2. TYPE OF WORK  DRILL NEW WELL ( REENTER P&A WELL ) DEEPEN WELL )									3. FIELD OR WILDCAT  ALTAMONT			
4. TYPE C	OF WELL			Coalbed Metha					5. UNIT or COMMUNIT	IZATION A	AGREEME	NT NAM	E
6. NAME	OF OPERATOR			Y E&P COMPAN					7. OPERATOR PHONE	713 997	-5038		
8. ADDRE	SS OF OPERAT	TOR		na, Houston, T					9. OPERATOR E-MAIL			om	
	RAL LEASE NUI			11. MIN	RAL OWNERSH	(E)		en.	12. SURFACE OWNERS	SHIP			-@
		Fee OWNER (if box 1:	2 = 'fee')	FEDE	RAL INDIA	AN [_] S	STATE FEE (I	A.	FEDERAL INC	PHONE (	STATE		E( <b>()</b> )
		ACE OWNER (if bo	Rie	chard Thorne					16. SURFACE OWNER	708-203	-5775		
			East Washingto										
	N ALLOTTEE C 2 = 'INDIAN')	OR TRIBE NAME			LE FORMATIONS	S	Application) NO	)	19. SLANT  VERTICAL DIR	RECTIONAL	н	ORIZONT	AL 💮
20. LOC	ATION OF WEL	L		FOOTAGES		QTR-Q	TR SECTI	ON	TOWNSHIP	RAI	NGE	МЕ	RIDIAN
LOCATION	ON AT SURFAC	E		900 FSL 1400	EL	SWSE	31		2.0 S	4.0	) W		U
Top of U	Jppermost Pro	ducing Zone		900 FSL 1400	EL	SWSE	31		2.0 S	4.0	) W		U
At Total	Depth			900 FSL 1400	EL EL	SWSE	31		2.0 S	4.0	) W	U	
21. COU	NTY	DUCHESNE		22. DIS1	ANCE TO NEAR	EST LEASE 900	LINE (Feet)		23. NUMBER OF ACRE	S IN DRIL		г	
					25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 2600				26. PROPOSED DEPTH MD:		TVD: 1260	00	
27. ELEV	ATION - GROU	ND LEVEL		28. BON	28. BOND NUMBER				29. SOURCE OF DRILL WATER RIGHTS APPRO			DI ICADI	
		6051			400JU0708				WATER RIGHTS AFFRO	Duchesn		FLICABL	
						10000010	10						
			7			and Ceme	ent Information						
String	Hole Size	Casing Size	Length	Weigh	t Grade & 1	and Ceme	ent Information Max Mud Wt.		Cement		Sacks	Yield	Weight
Cond	20	13.375	0 - 800	Weigh	t Grade & 1	and Ceme Thread .T&C	ent Information  Max Mud Wt.  8.8		Class G		1000	1.15	15.8
_		_		Weigh	t Grade & 1	and Ceme Thread .T&C	ent Information Max Mud Wt.	Pı		ength			
Cond	20	13.375	0 - 800	Weigh           54.5           40.0	J-55 L N-80 L	and Ceme Thread .T&C .T&C	ent Information  Max Mud Wt.  8.8		Class G 35/65 Poz		1000	1.15 3.16	15.8 11.0
Cond	20 12.25	13.375 9.625	0 - 800	<b>Weigh</b> 54.5	J-55 L N-80 L	and Ceme Thread .T&C .T&C	Max Mud Wt.  8.8  9.5	Pı	Class G 35/65 Poz remium Lite High Stre	ength	1000 560 191	1.15 3.16 1.33	15.8 11.0 14.2
Cond	20 12.25	13.375 9.625	0 - 800	Weigh 54.5 40.0 29.0	F-110	and Ceme Thread .T&C .T&C	Max Mud Wt.  8.8  9.5	Pı	Class G 35/65 Poz remium Lite High Stro remium Lite High Stro	ength	1000 560 191 378	1.15 3.16 1.33 2.31	15.8 11.0 14.2 12.0
Cond Surf	20 12.25 8.75	13.375 9.625 7	0 - 800 0 - 4000 0 - 9800	Weigh 54.5 40.0 29.0	F-110	and Ceme Thread .T&C .T&C	ent Information  Max Mud Wt.  8.8  9.5  10.8	Pı	Class G 35/65 Poz remium Lite High Stro remium Lite High Stro remium Lite High Stro	ength	1000 560 191 378 91	1.15 3.16 1.33 2.31 1.91	15.8 11.0 14.2 12.0 12.5
Cond Surf	20 12.25 8.75 6.125	13.375 9.625 7 5	0 - 800 0 - 4000 0 - 9800 9600 - 126	Weigh 54.5 0 40.0 0 29.0 600 13.5	P-110 I	and Cemo Thread T&C T&C LT&C LT&C TACHMEI	ent Information  Max Mud Wt.  8.8  9.5  10.8  13.5	Pi	Class G 35/65 Poz remium Lite High Stro remium Lite High Stro remium Lite High Stro	ength ength	1000 560 191 378 91 229	1.15 3.16 1.33 2.31 1.91	15.8 11.0 14.2 12.0 12.5
Cond Surf	20 12.25 8.75 6.125	13.375 9.625 7 5	0 - 800 0 - 4000 0 - 9800 9600 - 126	Weigh 54.5 0 40.0 0 29.0 0 13.5	The second of th	and Cemo Thread T&C T&C LT&C LT&C TACHMEI	ent Information  Max Mud Wt.  8.8  9.5  10.8  13.5  NTS	Pi Pi	Class G 35/65 Poz remium Lite High Stru remium Lite High Stru remium Lite High Stru 50/50 Poz	ength ength	1000 560 191 378 91 229	1.15 3.16 1.33 2.31 1.91	15.8 11.0 14.2 12.0 12.5
Cond Surf	20 12.25 8.75 6.125	13.375 9.625 7 5	0 - 800 0 - 4000 0 - 9800 9600 - 126	Weigh	The second of th	and Cemo Thread T&C T&C LT&C LT&C TACHMEI	ent Information  Max Mud Wt.  8.8  9.5  10.8  13.5  NTS  THE UTAH OIL AN	PI PI D GAS	Class G 35/65 Poz remium Lite High Stru remium Lite High Stru remium Lite High Stru 50/50 Poz	ength ength	1000 560 191 378 91 229	1.15 3.16 1.33 2.31 1.91	15.8 11.0 14.2 12.0 12.5
Cond Surf	20 12.25 8.75 6.125	13.375 9.625 7 5 RIFY THE FOLL	0 - 800 0 - 4000 0 - 9800 9600 - 126 DWING ARE A	Weigh	The state of the s	and Cemo Thread T&C T&C LT&C LT&C TACHMEI	ent Information  Max Mud Wt.  8.8  9.5  10.8  13.5  NTS  THE UTAH OIL ANI  COMPLETE DRIL  FORM 5. IF OPER	PI PI D GAS	Class G 35/65 Poz remium Lite High Stro remium Lite High Stro remium Lite High Stro 50/50 Poz	ength ength	1000 560 191 378 91 229	1.15 3.16 1.33 2.31 1.91	15.8 11.0 14.2 12.0 12.5
Cond Surf  I1  L1  L1  DI	20 12.25 8.75 6.125	13.375 9.625 7 5 RIFY THE FOLL MAP PREPARED BY	0 - 800 0 - 4000 0 - 9800 9600 - 126 DWING ARE A	Weigh 54.5 0 40.0 0 29.0 0 13.5  TTACHED IN EVEYOR OR ENGLISHED TO THE PERFORMANCE OF THE	The state of the s	and Ceme Thread T&C T&C T&C  LT&C  TACHMEI  E WITH T	ent Information  Max Mud Wt.  8.8  9.5  10.8  13.5  NTS  THE UTAH OIL ANI  COMPLETE DRIL  FORM 5. IF OPER	PI PI D GAS LING P	Class G 35/65 Poz remium Lite High Stro remium Lite High Stro remium Lite High Stro 50/50 Poz	ength ength	1000 560 191 378 91 229	1.15 3.16 1.33 2.31 1.91	15.8 11.0 14.2 12.0 12.5
Cond Surf  I1  L1  L1  AF	20 12.25 8.75 6.125  VEIL PLAT OR METABORITY OF ST	13.375 9.625 7 5 RIFY THE FOLL MAP PREPARED BY	0 - 800 0 - 4000 0 - 9800 9600 - 126 DWING ARE A	Weigh 54.5 0 40.0 0 29.0 0 13.5  TTACHED IN EVEYOR OR ENGLISHED TO THE PERFORMANCE OF THE	The state of the s	and Ceme Thread T&C T&C T&C  LT&C  TACHMEI  E WITH T	ent Information  Max Mud Wt.  8.8  9.5  10.8  13.5  NTS  THE UTAH OIL ANI  COMPLETE DRIL  FORM 5. IF OPER	PI PI D GAS LLING P ATOR I	Class G 35/65 Poz remium Lite High Stru remium Lite High Stru remium Lite High Stru 50/50 Poz	ength ength ENERAL	1000 560 191 378 91 229 RULES	1.15 3.16 1.33 2.31 1.91	15.8 11.0 14.2 12.0 12.5

# Thorne 3-31B4 Sec. 31, T2S, R4W DUCHESNE COUNTY, UT

# EP ENERGY E&P COMPANY, L.P.

### DRILLING PROGRAM

# 1. Estimated Tops of Important Geologic Markers

<u>Formation</u>	<u>Depth</u>	
Green River (GRRV) Green River (GRTN1) Mahogany Bench L. Green River Wasatch	4,818' 5,628' 6,668' 8,008' 9,818'	
T.D. (Permit)	12,600'	

# 2. Estimated Depths of Anticipated Water, Oil, Gas or Mineral Formations:

3' 3'
3'
8'
8'

# 3. Pressure Control Equipment: (Schematic Attached)

A 4.5" by 20.0" rotating head on structural pipe from surface to 800'. A 4.5" by 13 3/8" Smith Rotating Head and 5M Annular from 800' to 4,000' on Conductor. A 5M BOP stack, 5M Annular, and 5M kill lines and choke manifold used from 4,000' to 9,800'. A 10M BOE w/rotating head, 5M annular, blind rams & mud cross from 9,800' to TD. The BOPE and related equipment will meet the requirements of the 5M and 10M system.

# **OPERATORS MINIMUM SPECIFICATIONS FOR BOPE:**

The surface casing will be equipped with a flanged casing head of 5M psi working pressure. An 11" 5M x 11" 10M spool, 11" x 10M psi BOP and 5M psi Annular will be nippled up on the surface casing and tested to 250 psi low test / 3,000 psi high test for 10 minutes each prior to drilling out. The surface casing will be tested to 1,000 psi. for 30 mins. Intermediate casing will be tested to the greater of 1500 psi or 0.22 psi/ft. The choke manifold equipment, upper Kelly cock, floor safety valves will be tested to 5M psi. The annular preventer will be tested to 250 psi low lest and 4,000 psi high test. The 10M BOP will be installed

with 3 ½" pipe rams, blind rams, mud cross and rotating head from intermediate shoe to TD. The BOPE will be hydraulically operated.

In addition, the BOP equipment will be tested after running intermediate casing, after any repairs to the equipment and at least once every 30 days. Pipe and blind rams will be activated on each trip, annular preventer will be activated weekly and weekly BOP drills will be held with each crew.

# **Statement on Accumulator System and Location of Hydraulic Controls:**

Precision Rig # 404 is expected to be used to drill the proposed well. Operations will commence after approval of this application. Manual and/or hydraulic controls will be in compliance with 5M and 10M psi systems.

# **Auxiliary Equipment**:

- A) Pason monitoring systems with gas monitor 800 TD.
- B) Mud logger with gas monitor 4,000' to TD
- C) Choke manifold with one manual and one hydraulic operated choke
- D) Full opening floor valve with drill pipe thread
- E) Upper and lower Kelly cock
- F) Shaker, de-sander and de-silter, and centrifuge.

# 4. Proposed Casing & Cementing Program:

Please refer to the attached Wellbore Diagram.

All casing will meet or exceed the following design safety factors:

- Burst = 1.00
- Collapse = 1.125
- Tension = 1.2 (including 100k# overpull)

Cement design calculations will be based on: 25% excess over gauge hole in the liner section, 10% excess over gauge hole in the intermediate section, and 75% excess on the lead and 50% excess on the tail over gauge hole volume for the surface hole. Actual volumes pumped will be a minimum of the volumes stated above, however, actual hole size will be based on caliper logs in the liner and intermediate sections. Gauge hole will be used for the surface section.

# 5. **Drilling Fluids Program:**

Proposed Mud Program:

Interval	Туре	Mud Weight
Surface	WBM	8.8 – 9.5
Intermediate	WBM	9.5 – 10.8
Production	WBM	10.8 – 13.5

Anticipated mud weights are based on actual offset well bottom-hole pressure data. Mud weights utilized may be somewhat higher to allow for trip margin and to provide hole stability for running logs and casing.

Visual mud monitoring equipment will be utilized.

# 6. **Evaluation Program**:

Logs:

Mud Log: 4,000' - TD.

Open Hole Logs: Gamma Ray, Neutron-Density, Resistivity, Sonic, from base of surface casing to TD.

# 7. Abnormal Conditions:

Maximum anticipated bottomhole pressure calculated at 12,600' TD equals approximately 8,845 psi. This is calculated based on a 0.702 psi/foot gradient (13.5 ppg mud density at TD).

Maximum anticipated surface pressure equals approximately 6,073 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/ft).

Maximum anticipated surface pressure based on frac gradient at 7" casing shoe is 0.8 psi/ft at 9,800' = 7,840 psi


BOPE and casing design will be based on the lesser of the two MASPs which is 6,073 psi.

8. OPERATOR REQUESTS THAT THE PROPOSED WELL BE PLACED ON CONFIDENTIAL STATUS.

Page 1/2



# **Drilling Schematic**



Page 2/2

# DRILLING PROGRAM

CASING PROGRAM	SIZE	INTE	ERVAL	WT.	GR.	CPLG.	BURST	COLLAPSE	TENSION
CONDUCTOR	13 3/8"	0	800	54.5	J-55	LTC	2,730	1,140	1,399
SURFACE	9-5/8"	0	4000	40.00	N-80	LTC	3,090	5,750	820
INTERMEDIATE	7"	0	9800	29.00	P-110	LTC	11,220	8,530	797
PRODUCTION LINER	4 1/2"	9600	12600	13.50	P-110	LTC	12,410	10,680	338

CEMENT PROGRA	M	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
CONDUCTOR		800	Class G + 3% CACL2	1000	100%	15.8 ppg	1.15
SHDEACE	Lead 3,500 Boral Craig POZ 35%, Mountain G 65%, Bentonite Wyoming 8%, Silicate 5 lbm/sk, Pol-E Flake 0.125 lbm/sk, Kwik Seal 0.25 lb/sk		560	75%	11.0 ppg	3.16	
SURFACETail		500	Halco-light premium+3 lb/sk Silicate+0.3% Econolite+1% Salt+0.25 lbm/sk Kol- Seal+0.24 lb/sk Kwik Seal+ HR-5	191	50%	14.2 ppg	1.33
INTERMEDIATE	Lead	5,300	Hallco-Light-Premium+4% Bentonite+0.4% Econolite+0.2% Halad322+3 lb/sk Silicalite Compacted+0.8% HR-5+ 0.125 lb/sk Poly- E-Flake	378	10%	12.0 ppg	2.31
	Tail	1,000	Hallco-Light-Pternium+0.2% Econofite+ 0.3% Versaset+0.2% Halad322+0.8% HR- 5+ 0.3% SuperCBL+ 0.125 lb/sk Poly-E- Flake	91	10%	12.5 ppg	1.91
PRODUCTION LINER		3,000	Halco- 50/50 Poz Premium Cement+20% SSA-1+0.3% Super CBL+ 0.3% Halad- 344+0.3% Halad-413+ 0.2% SCR-100+ 0.125 lb/sk Poly-E-Flake + 3 lb/sk Silicat	229	25%	14.20	1.56

FLOAT EQUIPMENT & CE	INTRALIZERS TO THE PROPERTY OF
	PDC drillable guide shoe, 1 joint, PDC drillable float collar. Thread lock all float equipment. Install bow
OONDOOTOR	spring centralizers on the bottom 3 joints of casing.
SURFACE	PDC drillable guide shoe, 1 joint casing, PDC drillable float collar & Stage collar. Thread lock all float
SURFACE	equipment. Install bow spring centralizers on the bottom 3 joints of casing & every 3rd joint thereafter.
INTERMEDIATE	PDC drillable 10M,P-110 float shoe, 1 joint, PDC drillable 10M, P-110 float collar. Thread lock all float
INTERIVIEDIATE	equipment. Maker joint at 8,000'.
LINER	Float shoe, 1 joint, float collar. Thread lock all FE. Maker joints every 1000'.

 PROJECT ENGINEER(S):
 Joe Cawthorn
 713-997-5929

 MANAGER:
 Tommy Gaydos

# EP ENERGY E&P COMPANY, L.P. THORNE 3-31B4 SECTION 31, T2S, R4W, U.S.B.&M.

PROCEED NORTH ON PAVED STATE HIGHWAY 87 FROM THE INTERSECTION OF HIGHWAY 87 WITH U.S. HIGHWAY 40 IN DUCHESNE, UTAH APPROXIMATELY 5.96 MILES TO AN INTERSECTION;


TURN RIGHT AND TRAVEL SOUTHEASTERLY 0.67 MILES ON A GRAVEL ROAD TO AN INTERSECTION;

TURN LEFT AND TRAVEL EASTERLY 0.33 MILES ON A GRAVEL ROAD TO AN INTERSECTION;

TURN LEFT AND TRAVEL NORTH 0.80 MILES ON A GRAVEL ROAD TO THE BEGINNING OF THE ACCESS ROAD;

CONTINUE NORTH AND THEN WEST 0.50 MILES TO THE PROPOSED WELL LOCATION;

TOTAL DISTANCE FROM DUCHESNE, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 8.26 MILES.



# EP ENERGY E & P COMPANY, L.P. FIGURE #2

900' FSL, 1400' FEL

LOCATION LAYOUT FOR


THORNE 3-31B4

SECTION 31, T2S, R4W, U.S.B.&M.

X-SECTION
SCALE

1"=80'

NOTE: ALL CUT/FILL SLOPES ARE 1½:1 UNLESS OTHERWISE NOTED



## APPROXIMATE QUANTITIES

TOTAL CUT (INCLUDING PIT) = 8651 CU. YDS.

PIT CUT = 4572 CU. YDS.
TOPSOIL STRIPPING: (6") = 2494 CU. YDS.
REMAINING LOCATION CUT = 1585 CU. YDS

TOTAL FILL = 513 CU. YDS.

LOCATION SURFACE GRAVEL=1374 CU. YDS. (4" DEEP) ACCESS ROAD GRAVEL=711 CU. YDS.





JERRY D. ALLRED & ASSOCIATES
SURVEYING CONSULTANTS

1235 NORTH 700 EAST——P.O. BOX 975 DUCHESNE, UTAH 84021 (435) 738—5352


4 OCT 2012


01-128-318








# 5M BOP STACK and CHOKE MANIFOLD SYSTEM














# AFFIDAVIT OF DAMAGE SETTLEMENT AND RELEASE

Byron Moos personally appeared before me, and, being duly sworn, deposes and says:

- 1. My name is Byron Moos. I am over the age of 21 and am an Independent Oil and Gas Landman under contract with Transcontinent Oil Company acting as agent for EP Energy E&P Company, L.P., whose address is 1001 Louisiana Street, Houston, Texas 77002 ("EP Energy").
- 2. EP Energy is the operator of the proposed Thorne 3-31B4 well ("the Well") to be located on the East ½ of Lot 6 and on Lot 7 of Section 31, Township 2 South, Range 4 West, USM, Duchesne County, Utah (the "Drill site Location"). The surface owner of the Drill site Location is Richard Thorne, whose address is 21 East Washington Street, Villa Park, IL 60181-3019. The telephone contact number for Richard Thorne is (708) 203-5775.
- 3. EP Energy and the Surface Owner have entered into a Damage Settlement and Release Agreement dated March 1, 2013 to cover any and all injuries or damages of every character and description sustained by the Surface Owner or Surface Owner's property as a result of operations associated with the drilling, completion and producing the Well.

FURTHER AFFIANT SAYETH NOT.

Byron Moos

ACKNOWLEDGMENT


STATE OF UTAH

8

COUNTY OF DUCHESNE

This instrument was acknowledged before me on this the Lith day of March, 2013 by Byron Moos as an Independent Landman acting as agent for EP ENERGY E&P COMPANY, L.P on behalf of said partnership and acknowledged to me that he executed the same as his own free and voluntary act and deed for the uses and purposes therein set forth.

Notary Public in and for the State of Utah



API Well Number: 43013520860000 Application for Permit to Drill – State DOGM

Thorne 3-31B4
Duchesne County, Utah

# EP Energy E&P Company, L.P.

# **Related Surface Information**

# 1. <u>Current Surface Use:</u>

Livestock Grazing and Oil and Gas Production.

# 2. <u>Proposed Surface Disturbance:</u>

- The road will be crown and ditch. Water wings will be constructed on the access road as needed.
- The topsoil will be windrowed and re-spread in the borrow area.
- New road to be constructed will be approximately .50 miles in length and 66 feet wide.
- All equipment and vehicles will be confined to the access road, pad and area specified in the APD.

## 3. Location Of Existing Wells:

Existing oil, gas wells within one (1) mile radius of proposed well are provided in EXHIBIT C.

# 4. <u>Location And Type Of Drilling Water Supply:</u>

Drilling water: Duchesne City Water

# 5. Existing/Proposed Facilities For Productive Well:

- There are no existing facilities that will be utilized for this well.
- A pipeline corridor .50 miles will parallel the proposed access road. The corridor will contain one 4 inch gas line
  and one 2 inch gas line and one 2 inch Salt Water disposal line. Rehabilitation of unneeded, previously disturbed
  areas will consist of backfilling and contouring the reserve pit area; backsloping and contouring all cut and fill
  slopes. These areas will be reseeded. Refer to plans for reclamation of surface for details.
- Upgrade and maintain access roads and drainage control structures (e.g., culverts, drainage dips, ditching, etc.) as necessary to prevent soil erosion and accommodate safe, year-round traffic.

# 6. Construction Materials:

 Native soil from road and location will be used for construction materials along with gravel and/or scoria road base material. In the event that conditions should necessitate graveling of all or part of the access road and location, surfacing materials will be purchased from commercial suppliers in the marketing area.

# 7. Methods For Handling Waste Disposal:

- The reserve pit will be designed to prevent the collection of surface runoff and will be constructed with a minimum of ½ the total depth below the original ground surface on the lowest point with the pit. The pit will be lined with a 20-mil polyethylene to prevent leakage of fluids. The liner will be rolled into place and secured at the ends, i.e. buried on top of the pit berms. Prior to use, the reserve pit will be fenced on three sides; the fourth side will be fenced at the time the rig is removed. Drilling fluids, cuttings and produced water will be contained in the reserve pit (trash will be place in the trash cage). Fluids in the reserve pit will be allowed to evaporate prior to pit burial.
- Garbage and other trash will be contained in the portable trash cage and hauled off the location to an authorized disposal site. Any trash on the pad will be cleaned up prior to the rig moving off location and hauled to an authorized disposal site.
- Sewage will be handled in Portable Toilets.
- Produced water will be placed in the reserve pit for a period not to exceed ninety days after initial production. Any
  hydrocarbons produced during completion work will be contained in test tanks and removed from the location at a
  later date.
- Water from the reserve pit may be used for drilling of additional wells. The water will be trucked along access roads as approved in pertinent APD's

## 8. Ancillary Facilities:

There will be no ancillary facilities associated with this project.

RECEIVED: March 09, 2013

API Well Number: 43013520860000 Application for Permit to Drill – State DOGM Thorne 3-31B4

### 9. **Surface Reclamation Plans:**

Duchesne County, Utah

Backfilling of the pits will be done when dry. In the event of a dry hole, the location will be re-contoured, the topsoil will be distributed evenly over the entire location, and the seedbed prepared.

- Seed will be planted after September 15<sup>th</sup>, and prior to ground frost, or seed will be planted after the frost has left and before May 15<sup>th</sup>. Slopes to steep for machinery will be hand broadcast and raked with twice the specified amount of seed.
  - 1. The construction program and design are on the attached cut, fill and cross sectional diagrams.
  - 2. Prior to construction, all topsoil will be removed from the entire site and stockpiled. Topsoil for this site is the first 6 inches of soil materials.
  - 3. After the location has been reshaped and after redistributing the topsoil, the operator will rip and scarify the drilling platform and access road on the contour, to a depth of at least 12 inches.
- Rehabilitation will begin upon the completion of the drilling. Complete rehabilitation will depend on weather conditions and the amount of time required to dry the reserve pit.
  - 1. All rehabilitation work including seeding will be completed as soon as weather and the reserve pit conditions are appropriate.
  - 2. Landowner will be contacted for rehabilitation requirements.

### 10. **Surface Ownership:**

Richard Thorne 21 East Washington Street Villa Park, IL 60181-3019 708-203-5775

### Other Information:

- The surface soil consists of clay, and silt.
- Flora vegetation consists of the following: Sagebrush, Juniper and prairie grasses.
- Fauna antelope, deer, coyotes, raptors, small mammals, and domestic grazing animals.
- Current surface uses Livestock grazing and mineral exploration and production.

### **Operator and Contact Persons:**


**Construction and Reclamation:** EP Energy E&P Company, L.P. **Wayne Garner PO Box 410** Altamont, Utah 84001 435-454-3394 - Office

435-823-1490 - Cell

Drilling

EP Energy E&P Company, L.P. Joe Cawthorn - Drilling Engineer 1001 Louisiana, Rm 2523B Houston, Texas 77002 713-997-5929 - office 832-465-2882 - Cell

Regarding This APD EP Energy E&P Company, L.P. Maria S. Gomez 1001 Louisiana, Rm 2730D Houston, Texas 77002 713-997-5038 - Office



# BOPE REVIEW EP ENERGY E&P COMPANY, L.P. Thorne 3-31B4 43013520860000

Well Name	Well Name			EP ENERGY E&P COMPANY, L.P. Thorne 3-31B4 43013520860000					
				EP ENERGY E&P COMPANY, L.P. Thorne 3-31B4 43013520860000					
String		Cond	Surf	l1	<u>L1</u>				
Casing Size(")		13.375	9.625	7.000	5.000				
Setting Depth (TVD)	800	4000	9800	12600					
Previous Shoe Setting Depth	0	800	4000	9800					
Max Mud Weight (ppg)		8.8	9.5	10.8	13.5				
BOPE Proposed (psi)		1000	5000	5000	10000				
Casing Internal Yield (psi)		2730	5750	11220	12410				
Operators Max Anticipated	8845			13.5					
Calculations	Cond String 13.375								
Max BHP (psi)	.052*Setting Depth*MW=								


Calculations	Cond String	13.375	"
Max BHP (psi)	.052*Setting Depth*MW=	366	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	270	YES 4.5" by 20.0" rotating head
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	190	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting Depth - Previous Shoe Depth)=	190	NO
Required Casing/BOPE Test Pressure=			pși
*Max Pressure Allowed @	Previous Casing Shoe=	0	psi *Assumes 1psi/ft frac gradient

Calculations	Surf String		9.625	"
Max BHP (psi)	.052*Setting Depth*MW=	1976		
				BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	1496		YES 4.5 x 13 3/8
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	1096		YES OK
				*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting Depth - Previous Shoe Depth)=	1272		NO OK
Required Casing/BOPE Tes	st Pressure=	4000		psi
*Max Pressure Allowed @	Previ <mark>ou</mark> s Casing Shoe=	800		psi *Assumes 1psi/ft frac gradient

Calculations	I1 String	7.000	"
Max BHP (psi)	.052*Setting Depth*MW=	5504	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	4328	YES 5M BOP stack, 5M Annular, 5M kill lines,
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	3348	YES choke manifold
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting Depth - Previous Shoe Depth)=	4228	NO OK
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

Calculations	L1 String	5.000	"
Max BHP (psi)	.052*Setting Depth*MW=	8845	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	7333	YES 10M BOE w/rotating head, 5M annular, blind
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	6073	YES rams & mud cross
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting Depth - Previous Shoe Depth)=	8229	YES OK
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @	Previous Casing Shoe=	9800	psi *Assumes 1psi/ft frac gradient

# 43013520860000 Thorne 3-31B4



Well name:

43013520860000 Thorne 3-31B4

Operator:

EP ENERGY E&P COMPANY, L.P.

Conductor

Project ID:

String type:

43-013-52086

Location:

**DUCHESNE** COUNTY

Minimum design factors:

**Environment:** 

**Collapse** 

Mud weight:

Design parameters:

Collapse: Design factor H2S considered?

No

8.800 ppg

1.125

Surface temperature:

74 °F

Design is based on evacuated pipe.

Bottom hole temperature: Temperature gradient:

Non-directional string.

85 °F 1.40 °F/100ft

Minimum section length: 1,000 ft

Burst:

Design factor

1.00 Cement top: 242 ft

**Burst** 

Max anticipated surface

pressure:

270 psi

Internal gradient: Calculated BHP

0.120 psi/ft 366 psi

**Tension:** 

1.80 (J)

No backup mud specified.

8 Round STC:

8 Round LTC:

1.80 (J) 1.60 (J)

Buttress: Premium:

Body yield:

1,50 (J) 1.60 (B)

Tension is based on air weight. Neutral point: 696 ft

Segment		Nominal		End	True Vert	Measured	Drift	Est.	
Length	Size	Weight	Grade	Finish	Depth	Depth	Diameter	Cost	
(ft)	(in)	(lbs/ft)			(ft)	(ft)	(in)	(\$)	
800	13.375	54.50	J-55	ST&C	800	800	12.49	9926	
		17-11							
Collapse	Collapse	Collapse	Burst	Burst	Burst	Tension	Tension	Tension	
Load	Strength	Design	Load	Strength	Design	Load	Strength	Design	
(psi)	(psi)	Factor	(psi)	(psi)	Factor	(kips)	(kips)	Factor	
366	1130	3.090	366	2730	7.46	43.6	514	11.79 J	
	Length (ft) 800 Collapse Load (psi)	Length Size (ft) (in) 800 13.375  Collapse Collapse Load Strength (psi) (psi)	Length Size Weight (ft) (in) (lbs/ft) 800 13.375 54.50  Collapse Collapse Collapse Load Strength Design (psi) (psi) Factor	Length Size Weight Grade (ft) (in) (lbs/ft) 800 13.375 54.50 J-55  Collapse Collapse Collapse Burst Load Strength Design Load (psi) (psi) Factor (psi)	Length Size Weight Grade Finish (ft) (in) (lbs/ft) 800 13.375 54.50 J-55 ST&C  Collapse Collapse Collapse Burst Burst Load Strength Design Load Strength (psi) (psi) Factor (psi) (psi)	Length Size Weight Grade Finish Depth (ft) (in) (lbs/ft) (ft) (ft) (ft) (ft) 800 13.375 54.50 J-55 ST&C 800  Collapse Collapse Collapse Burst Burst Burst Load Strength Design Load Strength Design (psi) (psi) Factor (psi) (psi) Factor	Length (ft)Size (in)Weight (lbs/ft)Grade (red)Finish (in)Depth (ft)Depth (ft)80013.37554.50J-55ST&C800800CollapseCollapseCollapseBurstBurstBurstTensionLoadStrengthDesignLoadStrengthDesignLoad(psi)(psi)Factor(psi)Factor(kips)	Length (ft)Size (in)Weight (lbs/ft)Grade (lbs/ft)Finish (ft)Depth (ft)Depth (ft)Diameter (ft)80013.37554.50J-55ST&C80080012.49CollapseCollapseCollapseBurstBurstBurstTensionTensionLoadStrengthDesignLoadStrengthDesignLoadStrength(psi)(psi)Factor(psi)Factor(kips)(kips)	LengthSize (ft)Weight (lbs/ft)Grade (lbs/ft)Finish (ft)Depth (ft)Depth (ft)Diameter (ft)Cost (in)80013:37554:50J-55ST&C80080012:499926CollapseCollapseCollapseBurstBurstBurstTensionTensionTensionLoadStrengthDesignLoadStrengthDesignLoadStrengthDesign(psi)(psi)Factor(kips)(kips)Factor

Prepared

by:

Helen Sadik-Macdonald

Div of Oil, Gas & Mining

Phone: 801 538-5357 FAX: 801-359-3940

Date: April 24,2013 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 800 ft, a mud weight of 8.8 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

43013520860000 Thorne 3-31B4 Well name:

EP ENERGY E&P COMPANY, L.P. Operator:

Surface

String type: Project ID: 43-013-52086

DUCHESNE COUNTY Location:

**Environment: Design parameters:** Minimum design factors:

H2S considered? Collapse Collapse: No 74 °F Mud weight: 9.500 ppg Design factor 1.125 Surface temperature:

130 °F Design is based on evacuated pipe. Bottom hole temperature: Temperature gradient: 1.40 °F/100ft

Minimum section length: 100 ft

**Burst:** 

1.00 Design factor Cement top: Surface

8 Round STC:

Burst

Calculated BHP

Max anticipated surface pressure:

3,120 psi Internal gradient: 0.220 psi/ft Tension:

8 Round LTC: 1.70 (J) Buttress: 1.60 (J) No backup mud specified.

Premium: 1.50 (J) Body yield: 1.50 (B)

4,000 psi

Tension is based on air weight.

Re subsequent strings:

4,000 psi

Non-directional string.

Next setting depth: 9.800 ft Next mud weight: 10.800 ppg Neutral point: 3,435 ft Next setting BHP: 5,498 psi Fracture mud wt: 19.250 ppg 4,000 ft

Fracture depth: Injection pressure:

1.80 (J)

**Nominal** End True Vert Measured Drift Run Segment Est. Seq Length Size Weight Grade **Finish** Depth Depth Diameter Cost (ft) (in) (lbs/ft) (ft) (ft) (in) (\$) 1 4000 9.625 40.00 N-80 LT&C 4000 4000 8.75 50899 Run Collapse Collapse Collapse **Burst** Burst Burst **Tension Tension Tension** Seq Load Strength Design Load Strength Design Load Strength Design **Factor** (psi) **Factor** (kips) **Factor** (psi) (psi) (psi) (kips) 1974 4000 1 3090 1.565 1.44 160 4.61 J

5750

Prepared Helen Sadik-Macdonald Div of Oil, Gas & Mining by:

Phone: 801 538-5357 FAX: 801-359-3940

Date: April 24,2013 Salt Lake City, Utah

737

Remarks:

Collapse is based on a vertical depth of 4000 ft, a mud weight of 9.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

43013520860000 Thorne 3-31B4 Well name:

EP ENERGY E&P COMPANY, L.P. Operator:

Intermediate Project ID: String type: 43-013-52086

DUCHESNE COUNTY Location:

Minimum design factors: **Design parameters: Environment:** 

Collapse Collapse: H2S considered? No 74 °F 10.800 ppg Design factor 1.125 Surface temperature: Mud weight:

Bottom hole temperature: 211 °F Design is based on evacuated pipe.

Temperature gradient: 1.40 °F/100ft

Minimum section length: 1,000 ft Burst:

1.00 Cement top: 5,719 ft Design factor Burst

Max anticipated surface

pressure: 6,064 psi Internal gradient: 0.220 psi/ft **Tension:** Non-directional string.

Calculated BHP 8,220 psi 8 Round STC: 1.80 (J) 8 Round LTC: 1.80 (J)

Buttress: 1.60 (J) No backup mud specified. 1.50 (J) Premium:

1.60 (B) Body yield:

Tension is based on air weight.

Re subsequent strings: Next setting depth:

1.36

12,600 ft Next mud weight: 13.500 ppg Next setting BHP: Neutral point: 8,198 ft 8,836 psi Fracture mud wt: 19.250 ppg Fracture depth: 9,800 ft 9.800 psi Injection pressure:

284.2

End True Vert Measured Drift Est. Run Segment **Nominal** Length Weight Grade Finish Depth Depth Diameter Cost Seq Size (ft) (in) (lbs/ft) (ft) (ft) (in) (\$) 1 9800 29.00 P-110 LT&C 9800 9800 6.059 110667 Run Collapse Collapse Collapse **Burst Burst Burst Tension Tension** Tension Strength Seq Load Strength Design Load Strength Design Load Design (psi) **Factor** (psi) (psi) **Factor** (kips) (kips) **Factor** (psi)

11220

8220

Helen Sadik-Macdonald Prepared Div of Oil, Gas & Mining by:

8530

1.551

Phone: 801 538-5357 FAX: 801-359-3940

Date: April 24,2013 Salt Lake City, Utah

797

2.80 J

Remarks:

1

5498

Collapse is based on a vertical depth of 9800 ft, a mud weight of 10.8 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Well name: 43013520860000 Thorne 3-31B4

Operator: EP ENERGY E&P COMPANY, L.P.

Operation. Dresduction Lines

String type: Production Liner Project ID: 43-013-52086

Location: DUCHESNE COUNTY

No backup mud specified.

Design parameters: Minimum design factors: Environment:

CollapseCollapse:H2S considered?NoMud weight:13.500 ppgDesign factor1.125Surface temperature:74 °F

Design is based on evacuated pipe. Bottom hole temperature: 250 °F
Temperature gradient: 1.40 °F/100ft

Minimum section length: 1,000 ft

1.60 (J)

Burst:

Design factor 1.00 Cement top:

**Buttress:** 

Design factor 1.00 Cement top: 10,157 ft

Burst
Max anticipated surface

pressure: 6,064 psi Liner top: 9,600 ft nternal gradient: 0.220 psi/ft **Tension: Non-directional string**.

Internal gradient: 0.220 psi/ft Calculated BHP 8,836 psi 8 Round STC: 1.80 (J) 1.80 (J) 1.80 (J)

Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight. Neutral point: 12,002 ft

Run	Segment		Nominal		End	True Vert	Measured	Drift	Est.	
Seq	Length	Size	Weight	Grade	Finish	Depth	Depth	Diameter	Cost	
	(ft)	(in)	(lbs/ft)			(ft)	(ft)	(in)	(\$)	
1	3000	4.5	13.50	P-110	LT&C	12600	12600	3.795	16810	
		,								
Run	Collapse	Collapse	Collapse	Burst	Burst	Burst	Tension	Tension	Tension	
Seq	Load	Strength	Design	Load	Strength	Design	Load	Strength	Design	
	(psi)	(psi)	Factor	(psi)	(psi)	Factor	(kips)	(kips)	Factor	
1	8836	10680	1.209	8836	12410	1.40	40.5	338	8.35 J	

Prepared Helen Sadik-Macdonald by: Div of Oil, Gas & Mining

Phone: 801 538-5357 FAX: 801-359-3940 Date: April 24,2013 Salt Lake City, Utah

Remarks:

For this liner string, the top is rounded to the nearest 100 ft.Collapse is based on a vertical depth of 12600 ft, a mud weight of 13.5 ppg. The Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

# **ON-SITE PREDRILL EVALUATION**

# Utah Division of Oil, Gas and Mining

**Operator** EP ENERGY E&P COMPANY, L.P.

Well Name Thorne 3-31B4

API Number 43013520860000 APD No 7785 Field/Unit ALTAMONT

**Location: 1/4,1/4** SWSE **Sec** 31 **Tw** 2.0S **Rng** 4.0W 900 FSL 1400 FEL

GPS Coord (UTM) Surface Owner Richard Thorne

# **Participants**

Wayne Garner (E&P Energy); Dennis Ingram (DOGM)

# Regional/Local Setting & Topography

The Thorne 3-31B4 well is proposed in northeastern Utah 5.96 miles north of Duchesne along Highway 87, then east along a gravel country road 1.0 mile, then north 1.3 miles on Blue Bench. The surface at the proposed well pad slopes gently to the south, having fine-grained blow sand for soils and greasewood/sagebrush vegetation at the surface. To the north, the elevation rises into broken, sandstone shelf habitat that is typically found along the northern surface of Blue Bench. The Duchesne County Landfill is located less than a mile to the northeast. A quarter mile to the west Highway 87 runs north/south, and further west Benson Draw drains the Talmage area to the south into the Duchesne River Basin.

# Surface Use Plan

**Current Surface Use** 

Wildlfe Habitat Recreational

New Road

Miles

Well Pad

**Src Const Material** 

**Surface Formation** 

0.5

Width 342 Length 425

Onsite

**UNTA** 

Ancillary Facilities N

Waste Management Plan Adequate?

Y

# **Environmental Parameters**

Affected Floodplains and/or Wetlands N

# Flora / Fauna

Greasewood, sagebrush, bunch grass, rabbit brush, prickly pear cactus; potential elk, mule deer, coyote, rabbit, fox, prairie dog, badger, other smaller mammals, hawk, eagle and other birds native to region.

# Soil Type and Characteristics

Reddish, fine-grained blow sand with some clays

**Erosion Issues** Y

Sedimentation Issues Y

Site Stability Issues N

RECEIVED: April 30, 2013

Drainage Diverson Required? N

Berm Required? Y

**Erosion Sedimentation Control Required?** N

Paleo Survey Run? N Paleo Potental Observed? N Cultural Survey Run? N Cultural Resources? N

# Reserve Pit

Site-Specific Factors	Site Rai	nking	
Distance to Groundwater (feet)	> 200	0	
Distance to Surface Water (feet)	>1000	0	
Dist. Nearest Municipal Well (ft)	>5280	0	
Distance to Other Wells (feet)	>1320	0	
Native Soil Type	High permeability	20	
Fluid Type	Fresh Water	5	
Drill Cuttings	Normal Rock	0	
Annual Precipitation (inches)		0	
Affected Populations			
Presence Nearby Utility Conduits	Not Present	0	
	Final Score	25	1 Sensitivity Level

# Characteristics / Requirements

Reserve pit proposed north of pad in cut, measuring 150' long by 110' wide by 12' deep, and having prevailing winds from the west

Closed Loop Mud Required? Liner Required? Y Liner Thickness 20 Pit Underlayment Required?

# Other Observations / Comments

Surface slopes to the south, soils are loose, reddish blow sands, Highway 87 a quarter mile west of site, county dump northeast of site, trash litters west side of surface, see photos

Dennis Ingram 4/3/2013
Evaluator Date / Time

RECEIVED: April 30, 2013

# **Application for Permit to Drill** Statement of Basis

# Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner CBM			
7785	43013520860000	LOCKED	OW	P No			
Operator	EP ENERGY E&P COMPANY	, L.P.	Surface Owner-APD	Richard Thorne			
Well Name	Thorne 3-31B4		Unit				
Field	ALTAMONT		Type of Work	DRILL			
Location	SWSE 31 2S 4W U	900 FSL 14	00 FEL GPS Coord				
Location	(UTM) 553169E 4456679N						

# **Geologic Statement of Basis**

EP proposes to set 800 feet of conductor and 4,000 feet of surface casing both of which will be cemented to surface. The surface and intermediate holes will be drilled utilizing fresh water mud. The estimated depth to the base of moderately saline ground water is 1,900 feet. A search of Division of Water Rights records indicates that there are 18 water wells within a 10,000 foot radius of the center of Section 31. Wells range between 83 and 500 feet in depth and are used for irrigation, stock watering, domestic, industrial, oil exploration and municipal. These wells probably produce from the Duchesne River Formation. The Duchesne River Formation is made up of sandstones with interbedded shales and is the most prominent fresh water aguifer in the area. The proposed casing and cement program should adequately protect ground water in this area.

> Brad Hill 4/11/2013 APD Evaluator Date / Time

# **Surface Statement of Basis**

A presite visit was scheduled for April 3, 2013 to take input and address issues regarding the permitting and construction of this well pad. Richard Thorne was shown as the landowner of record and therefore invited to the presite visit.

The surface at this site slopes gently to the south, having only 2.9 feet of cut along the northern border and 1.5 feet of fill on the southeastern corner. No drainage issues were found in the project area. Soils are fine-grained, reddish blow sand with greasewood and sagebrush making up most of the vegetation. The reserve pit is staked off the north side of the location, in cut, and will require a 20 mil synthetic liner to hold water. Topsoil stockpile shall be stored east of the reserve pit between corners 5 and 6. The location shall be bermed to prevent spills or leaks from leaving well pad. No other issues were noted at the presite meeting.

> 4/3/2013 Dennis Ingram Date / Time **Onsite Evaluator**

# Conditions of Approval / Application for Permit to Drill

Category Condition

A synthetic liner with a minimum thickness of 20 mils shall be properly installed and maintained in Pits

the reserve pit.

The reserve pit should be located on the north side of the location. Pits The well site shall be bermed to prevent fluids from leaving the pad. Surface

RECEIVED: April 30, 2013

# **WORKSHEET** APPLICATION FOR PERMIT TO DRILL


**APD RECEIVED: 3/9/2013** API NO. ASSIGNED: 43013520860000 WELL NAME: Thorne 3-31B4 OPERATOR: EP ENERGY E&P COMPANY, L.P. (N3850) PHONE NUMBER: 713 997-5038 CONTACT: Maria S. Gomez PROPOSED LOCATION: SWSE 31 020S 040W Permit Tech Review: **SURFACE: 0900 FSL 1400 FEL** Engineering Review: BOTTOM: 0900 FSL 1400 FEL Geology Review: **COUNTY: DUCHESNE LATITUDE: 40.25889** LÓNGITUDE: -110.37476 **UTM SURF EASTINGS: 553169.00** NORTHINGS: 4456679.00 FIELD NAME: ALTAMONT LEASE TYPE: 4 - Fee **LEASE NUMBER:** Fee PROPOSED PRODUCING FORMATION(S): GREEN RIVER(LWR)-WASATCH SURFACE OWNER: 4 - Fee **COALBED METHANE: NO RECEIVED AND/OR REVIEWED: LOCATION AND SITING:** ✓ PLAT R649-2-3. Bond: STATE/FEE - 400JU0708 Unit: Potash R649-3-2. General Oil Shale 190-5 Oil Shale 190-3 R649-3-3. Exception Oil Shale 190-13 **Drilling Unit** Board Cause No: Cause 139-84 Water Permit: Duchesne City **Effective Date: 12/31/2008 RDCC Review:** Siting: 4 Prod LGRRV-WSTC Wells **Fee Surface Agreement** Intent to Commingle R649-3-11. Directional Drill

Comments: Presite Completed

**Commingling Approved** 

Stipulations:

5 - Statement of Basis - bhill8 - Cement to Surface -- 2 strings - hmacdonald12 - Cement Volume (3) - ddoucet



# State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

# Permit To Drill

\*\*\*\*\*\*

Well Name: Thorne 3-31B4 **API Well Number:** 43013520860000

Lease Number: Fee

**Surface Owner:** FEE (PRIVATE) **Approval Date:** 4/30/2013

## Issued to:

EP ENERGY E&P COMPANY, L.P., 1001 Louisiana, Houston, TX 77002

# Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 139-84. The expected producing formation or pool is the GREEN RIVER(LWR)-WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

# **Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

# **Conditions of Approval:**

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Cement volumes for the 13 3/8" and 9 5/8" casing strings shall be determined from actual hole diameters in order to place cement from the pipe setting depths back to the surface.

Cement volume for the 7" casing string shall be determined from actual hole diameter in order to place cement from the pipe setting depth back to 3500' MD as indicated in the submitted drilling plan.

# **Additional Approvals:**

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan contact Dustin Doucet
- Significant plug back of the well contact Dustin Doucet
- Plug and abandonment of the well contact Dustin Doucet

# **Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

• Within 24 hours following the spudding of the well - contact Carol Daniels OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website

at http://oilgas.ogm.utah.gov

- 24 hours prior to testing blowout prevention equipment contact Dan Jarvis
- 24 hours prior to cementing or testing casing contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program
  - contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well contact Dan Jarvis

# **Contact Information:**

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 office
- Dustin Doucet 801-538-5281 office

801-733-0983 - after office hours

• Dan Jarvis 801-538-5338 - office

801-231-8956 - after office hours

# Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) due within 5 days of spudding the well
- Monthly Status Report (Form 9) due by 5th day of the following calendar month
  - Requests to Change Plans (Form 9) due prior to implementation
  - Written Notice of Emergency Changes (Form 9) due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) due prior to implementation
  - Report of Water Encountered (Form 7) due within 30 days after completion
- Well Completion Report (Form 8) due within 30 days after completion or plugging

Annuared Dr.

Approved by:

For John Rogers Associate Director, Oil & Gas



# SWEE SO 31 TOUS ROYW



# Notice of Spudding of Well: Thorne 3-31B4

RLANDRIG008 < RLANDRIG008@epenergy.com>

Wed, Aug 14, 2013 at 8:16 PM

To: Alexis Huefner <alexishuefner@utah.gov>, Carol Daniels <caroldaniels@utah.gov>, Dennis Ingram <dennisingram@utah.gov>, "Evans, Perry (Contractor)" <Perry.Evans@epenergy.com>, "Gaydos, Tommy L" <Tommy.Gaydos@epenergy.com>, "MacAfee, Bradley D" <Brad.MacAfee@epenergy.com>, "Morales, Lisa" <Lisa.Morales@epenergy.com>, "Gomez, Maria S" <Maria.Gomez@epenergy.com>

Aug. 14, 2013

This is notice of Spudding of the following well.

Well: Thorne 3-31 **34** 

API#43013520860000

County: Duchesne

Rig: Bucket Rig #33 of Leon Ross Drilling bucket rig.

Spud in at 1:00 PM Aug. 13, 2013

Best Regards

Steven Murphy

Rig Site Supervisor

EP Energy

C: 435-823-1725


RECEIVED

Also 1 9 2273

DIV. OF OIL, GAS & MINING

THIS E-MAIL AND ANY MATERIALS TRANSMITTED WITH IT MAY CONTAIN CONFIDENTIAL OR PROPRIETARY MATERIAL FOR THE SOLE USE OF THE INTENDED RECIPIENT. ANY REVIEW, USE, DISTRIBUTION OR DISCLOSURE BY OTHERS IS STRICTLY PROHIBITED. IF YOU ARE NOT THE INTENDED RECIPIENT, OR AUTHORIZED TO RECEIVE THE INFORMATION FROM THE RECIPIENT, PLEASE NOTIFY THE SENDER BY REPLY E-MAIL AND DELETE ALL COPIES OF THIS MESSAGE.

1/1



# 24 Hr Notice of Run'g & Cmt'g 7" Intermediate Casing on the Thorne 3-31B4 Test 11" 10 K BOPE 12 Hrs later.

# RLANDRIG008 < RLANDRIG008@epenergy.com>

Fri, Sep 13, 2013 at 7:45 PM

To: Alexis Huefner <alexishuefner@utah.gov>, Dennis Ingram <dennisingram@utah.gov>, Carol Daniels <caroldaniels@utah.gov>, "Evans, Perry (Contractor)" <Perry.Evans@epenergy.com>, "Gaydos, Tommy L" <Tommy.Gaydos@epenergy.com>, "MacAfee, Bradley D" <Brad.MacAfee@epenergy.com>, "Gomez, Maria S" <Maria.Gomez@epenergy.com>, "Morales, Lisa" <Lisa.Morales@epenergy.com>

Sept. 13, 2013

Well: Thorne 3-31 34

API# 43013520860000

County: Duchesne

Rig: Precision Drilling Rig #404

24 Hrs Notice for running and cementing of 7" Intermediate Casing 9,760' MD. Will be testing 11" 10 K BOPE 12 Hrs later.

Best Regards

Steven Murphy

Rig Site Supervisor

EP Energy

C: 435-823-1725

RECEIVED

SEP 1 3 2013

DIV. OF OIL, GAS & MINING

THIS E-MAIL AND ANY MATERIALS TRANSMITTED WITH IT MAY CONTAIN CONFIDENTIAL OR PROPRIETARY MATERIAL FOR THE SOLE USE OF THE INTENDED RECIPIENT. ANY REVIEW, USE, DISTRIBUTION OR DISCLOSURE BY OTHERS IS STRICTLY PROHIBITED. IF YOU ARE NOT THE INTENDED RECIPIENT, OR AUTHORIZED TO RECEIVE THE INFORMATION FROM THE RECIPIENT, PLEASE NOTIFY THE SENDER BY REPLY E-MAIL AND DELETE ALL COPIES OF THIS MESSAGE.

	STATE OF UTAH		FORM 9
1	DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	3	5.LEASE DESIGNATION AND SERIAL NUMBER: Fee
SUNDR	RY NOTICES AND REPORTS ON	WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for procurrent bottom-hole depth, FOR PERMIT TO DRILL form	7.UNIT or CA AGREEMENT NAME:		
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: Thorne 3-31B4		
2. NAME OF OPERATOR: EP ENERGY E&P COMPANY,	<b>9. API NUMBER:</b> 43013520860000		
3. ADDRESS OF OPERATOR: 1001 Louisiana , Houston,		ONE NUMBER: Ext	9. FIELD and POOL or WILDCAT: ALTAMONT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0900 FSL 1400 FEL			COUNTY: DUCHESNE
QTR/QTR, SECTION, TOWNSH Qtr/Qtr: SWSE Section: 3	HIP, RANGE, MERIDIAN: 31 Township: 02.0S Range: 04.0W Meridian:	: U	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICATE N	IATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	CHANGE TO PREVIOUS PLANS  CHANGE WELL STATUS  DEEPEN  OPERATOR CHANGE  PRODUCTION START OR RESUME  REPERFORATE CURRENT FORMATION  TUBING REPAIR  WATER SHUTOFF	_	CASING REPAIR  CHANGE WELL NAME  CONVERT WELL TYPE  NEW CONSTRUCTION  PLUG BACK  RECOMPLETE DIFFERENT FORMATION  TEMPORARY ABANDON  WATER DISPOSAL  APD EXTENSION  OTHER: Initial Completion  Depths, volumes, etc.  Approved by the Utah Division of Oil, Gas and Mining  Date: October 11, 2013  By:
NAME (PLEASE PRINT)	PHONE NUMBER	TITLE	
Maria S. Gomez	713 997-5038	Principal Regulatory Analys	t
<b>SIGNATURE</b> N/A		<b>DATE</b> 10/11/2013	

# Thorne 3-31 B4 Initial Completion 43-013-52086

#### The following precautions will be taken until the RCA for the Conover is completed:

- 1. Review torque turning and running of the 7" and 5" liner of anomalies.
- 2. Test and chart casing for 30 minutes, noting pressure if any on surface casing.
- 3. Test all lubricators, valves and BOP's to working pressure.
- 4. Wellhead isolation tools will continue to be used to isolate the wellhead during the frac.
- 5. Monitor the surface casing during frac:
  - a. Lay a flowline to the flow back tank and keep the valve open.
  - b. This line will remain in place until a wire line set retrievable packer is in place isolating the 5" casing from the 7" after the frac.
- 6. 2 7/8" tubing will be run to isolate the 7" casing during the flow back of the well.
- 7. Well pressure and annulus pressure would be monitored during this time until the well is ready for pump.

#### **Completion Information (Wasatch Formation)**

- Stage 1: RU WL unit with 10K lubricator and test to 10,000 psi with water. Perforations from ~12,436' 12,105' with ~5,000 gallons of 15% HCL acid, ~3,000# of 100 mesh sand and ~150,000# PowerProp 20/40.
- Stage 2: RU 10K lubricator and test to 10,000 psi with water. Set 10K CBP @ ~12,078'. Test CBP and casing to 8,500 psi. Perforations from ~12,069' 11,746' with ~5,000 gallons of 15% HCL acid, ~3,000# of 100 mesh sand and ~150,000# PowerProp 20/40.
- Stage 3: RU 10K lubricator and test to 10,000 psi with water. Set 10K CBP @  $^{\sim}$ 11,715′. Test CBP and casing to 8,500 psi. Perforations from  $^{\sim}$ 11,706 11,409′ with  $^{\sim}$ 5,000 gallons of 15% HCL acid,  $^{\sim}$ 3,000# of 100 mesh sand and  $^{\sim}$ 155,000# PowerProp 20/40.
- Stage 4: RU 10K lubricator and test to 10,000 psi with water. Set 10K CBP @ ~11,357'. Test CBP and casing to 8,500 psi. Perforations from ~11,347' 11,118' with ~5,000 gallons of 15% HCL acid, ~3,000# of 100 mesh sand and ~150,000# PowerProp 20/40.
- Stage 5: RU 10K lubricator and test to 10,000 psi with water. Set 10K CBP @ ~10,993'. Test CBP and casing to 8,500 psi. Perforations from ~11,083' 10,795' with ~5,000 gallons of 15% HCL acid, ~3,000# of 100 mesh sand and ~155,000# PowerProp 20/40.
- Stage 6: RU 10K lubricator and test to 10,000 psi with water. Set 10K CBP @ ~10,774′. Test CBP and casing to 8,500 psi. Perforations from ~10,764′ 10,486′ with ~5,000 gallons of 15% HCL acid, ~3,000# of 100 mesh sand and ~155,000# PowerProp 20/40.
- Stage 7: RU 10K lubricator and test to 10,000 psi with water. Set 10K CBP @ ~10,464'. Test CBP and casing to 8,500 psi. Perforations from ~10,456' 10,189' with ~5,000 gallons of 15% HCL acid, ~3,000# of 100 mesh sand and ~160,000# PowerProp 20/40.

Stage 8: RU 10K lubricator and test to 10,000 psi with water. Set 10K CBP @ ~10,151'. Test CBP

and casing to 8,500 psi. Perforations from ~10,139' – 9,873' with ~5,000 gallons of 15%

HCL acid, ~3,000# of 100 mesh sand and ~165,000# PowerProp 20/40.

RECEIVED: Oct. 11, 2013



#### **Current Wellbore Schematic**

Company Name: EP Energy

Well Name: Thorne 3-31 B4

Field, County, State: Altamont - Bluebell, Duchesne, Utah

Surface Location: Lat: 40° 15' 31.95974" N Long: 110° 22' 28.90789" W

Producing Zone(s): Wasatch


Last Updated: 9/27/2013

By: Robert Fondren

TD: 12,550'


BHL:

Elevation: 6,051'





#### **Initial Completion Wellbore Schematic**



(5/2000)

Directional survey not attached

STATE OF UTAH  DEPARTMENT OF NATURAL RESOURCES														REPOR changes)	Т	FO	RM 8
			IVISION	OF OIL,	GAS	AND N	IININ	3				5. LEA	SE DES	SIGNATION	AND SE	RIAL NUMB	ER:
WELL	CON	MPLET	ION OR	RECO	MPL	ETIO	N RE	POF	RT AND	LOG		6. IF II	NDIAN,	ALLOTTEE	OR TRIB	E NAME	(
1a. TYPE OF WELL:		OII	LL 🔽	GAS WELL	]	DRY [		ОТН	ER			7. UNI	7. UNIT or CA AGREEMENT NAME				
b. TYPE OF WORK:  NEW HORIZ. DEEP- RE- ENTRY DIFF.  OTHER														E and NUM e 3-31B			
2. NAME OF OPERATOR:													NUMBE				
EP Energy E&P Company, L.P.  3. ADDRESS OF OPERATOR: PHONE NUMBER:														52086 POOL, OR	WILDCA	т	
3. ADDRESS OF OPERATOR: 1001 Louisiana CITY Houston STATE TX ZIP 77002 PHONE NUMBER: (713) 997-5038												A	Itamo	ont			
4. LOCATION OF WI AT SURFACE:	900 FS	SL & 140					MIII		mentar Nation			THE COOP		SECTION, 1: 31 2		HIP, RANGE	
AT TOP PRODUC	CING INTE	RVAL REPOR	RTED BELOW:	900 FS	L & 14	100 FE	L								- 1		
AT TOTAL DEPT	H: 900	FSL & 1	1400 FEL									100000	ounty uches	sne	18	B. STATE	JTAH
14. DATE SPUDDED 8/27/2013	):	15. DATE T. 9/21/2	D. REACHED: 013	16. DATE	COMPL 17/201		А	BANDON	ED 🗌	READY TO	PRODUC			vations (E 051	F, RKB,	RT, GL):	
18. TOTAL DEPTH:	MD 1	2,550	19. PL	JG BACK T.D	.: MD			20. IF	MULTIPLE CO	MPLETION	S, HOW N	MANY? * 2		TH BRIDGE UG SET:			
AN TYPE ELECTRIC		2.543	ICAL LOCS BU	NI /Cubmit aga	TVD			<u> </u>	23.						TVD		
Sonic, Gami									WAS WELL		Y?	NO NO		YES T	(Subm	it analysis) it report) it copy)	
24. CASING AND LI	NER RECO	ORD (Report	all strings set i	well)													
HOLE SIZE	SIZE/G	SRADE	WEIGHT (#/ft.)	TOP (	MD)	вотто	M (MD)		CEMENTER CEMENT TYPE & NO. OF SACKS		SLURRY VOLUME (BBL) CEMENT TO		TOP **	AMOUNT	PULLED		
17.5	13.375	J55	54.5	C	)	68	31			G	900	1,03		C			
12.25	9.625	N80	40	0		3,6				Prem	705	91		0			
8.75	7"	P110	29	0		_	60			G	540	1,20		663			
6.125	5	P110	18	9,5	04	12,	550			Prem	225	33	1	~95	04		
9																	
25. TUBING RECOR	RD																
SIZE	-	H SET (MD)	PACKER SE		SIZE		DEPTH	SET (MD	) PACKEI	R SET (MD)	-	SIZE		DEPTH SET	(MD)	PACKER S	ET (MD)
2.875		),427	9,41	1							<u> </u>						
26. PRODUCING IN		TOP	(MD) I BO	TTOM (MD)	TOP	(TVD)	BOTTO	M (TVD)	27. PERFO	L (Top/Bot -		SIZE	NO. HOL	ES	DEBEOR	ATION STA	TUS
(A) Wasatch	INAME			2.436		775	12,4	8 2	12.105	- 15 O	,436	.43	69			Squeezed	
(B)		3,1	01	2,430	0,	-	12,	720	11,726		,069	.43	69			Squeezed	$\exists$
(C)		-							11,720		.706	.43	69	_		Squeezed	<u> </u>
(D)		+							11,117		,346	.43	69			Squeezed	_
28. ACID, FRACTUR	RE TREAT	MENT CEME	NT SOLIFEZE	etc See	at	tach	ed f	or :				natio				#28.	
	INTERVAL		1						OUNT AND T		TERIAL		_			155	
F			5000 99	I 15% H	CL 20	14 306	0# 10					wor Dro	n				
12105-12436				1 15% H													
11382-1170			5000 ga		10.000				10								
29. ENCLOSED AT		TS: All										VCITIO	Ρ	1:	30. WELI	STATUS:	
ELECT	RICAL/MEG	CHANICAL LO						C REPOR	т 🔲	DST REPOR		DIRECT	IONAL S			oduci	ng

(CONTINUED ON BACK)

31. INITIAL PRO	DDUCTION			INT	ERVAL A (As sho	wn in item #26)				
DATE FIRST PR 10/18/201		TEST DATE: 10/29/20	13	HOURS TESTED	o: 24	TEST PRODUCTION RATES: →	OIL – BBL: 659	GAS – MCF: 957	WATER – BBL: 409	PROD. METHOD: Flowing
CHOKE SIZE:	TBG. PRESS. 2,345	CSG. PRESS.	API GRAVITY 45.70	BTU – GAS 1	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL: 659	GAS - MCF: 957	WATER – BBL: 409	Producing
	2,010		10.70	100	ERVAL B (As sho	wn in item #26)				
DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:
				INT	ERVAL C (As sho	wn in item #26)				
DATE FIRST PR	ODUCED:	TEST DATE:		HOURS TESTED	);	TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG, PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:
		•		INT	ERVAL D (As sho	wn in item #26)				
DATE FIRST PR	ODUCED:	TEST DATE:		HOURS TESTED	D;	TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:
32. DISPOSITIO	ON OF GAS (Sold,	Used for Fuel, V	ented, Etc.)	•		•				
33. SUMMARY	OF POROUS ZON	IES (Include Aqu	ifers):			3	34. FORMATION (	Log) MARKERS:		
			ereof: Cored interva ut-in pressures and		n tests, including de	epth interval				
Formation	on		Bottom (MD)	Descrip	tions, Contents, etc.	Ċ:		Name		Top (Measured Depth)
Upper Green River 4,865 Middle Green River 6,556 Lower Green River 7,999 Wasatch 9,781								6,556 7,999		
36. I hereby ce	rtify that the fore	going and attach	ed information is o	complete and corr	ect as determined	l from all available rec	ords.			
-			ez Mara a				cipal Regula	atory Analys	st	

This report must be submitted within 30 days of

- · completing or plugging a new well
- · drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- · reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests
- \* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\*ITEM 24: Cement Top - Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to:

SIGNATURE

Utah Division of Oil, Gas and Mining 1594 West North Temple, Suite 1210

Box 145801

Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

(5/2000)

RECEIVED: Dec. 31, 2013

## **Attachment to Well Completion Report**

## Form 8 Dated December 20, 2013

Well Name: Thorne 3-31B4

## Items #27 and #28 Continued

## 27. Perforation Record

Interval (Top/Bottom – MD)	Size	No. of Holes	Perf. Status
10793'-11082'	.43	69	Open
10484'-10762'	.43	69	Open
9869'-10135'	.43	69	Open

## 28. Acid, Fracture, Treatment, Cement Squeeze, Etc.

<b>Depth Interval</b>	Amount and Type of Material
11117'-11346'	5000 gal 15% HCL acid, 3000# 100 Mesh, 150480# 20/40
	Power Prop
10793'-11082'	5000 gal 15% HCL acid, 3000# 100 Mesh, 155140# 20/40
	Power Prop
10484'-10762'	5000 gal 15% HCL acid, 3000# 100 Mesh, 160000# 20/40
	Power Prop
10186'-10453'	5000 gal 15% HCL acid, 3500# 100 Mesh, 160300# 20/40
	Tempered LC
9869'-10135'	5000 gal 15% HCL acid, 3500# 100 Mesh, 164740# 20/40
	Tempered LC

	STATE OF UTAH		FORM 9
ı	DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MININ		5.LEASE DESIGNATION AND SERIAL NUMBER: Fee
SUNDR	Y NOTICES AND REPORTS OF	N WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for pro current bottom-hole depth, FOR PERMIT TO DRILL form	7.UNIT or CA AGREEMENT NAME:		
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: Thorne 3-31B4		
2. NAME OF OPERATOR: EP ENERGY E&P COMPANY,	9. API NUMBER: 43013520860000		
3. ADDRESS OF OPERATOR: 1001 Louisiana, Houston,		HONE NUMBER: 3 Ext	9. FIELD and POOL or WILDCAT: ALTAMONT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0900 FSL 1400 FEL			COUNTY: DUCHESNE
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 31 Township: 02.0S Range: 04.0W Meridia	n: U	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
Approximate date work will start:	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
✓ SUBSEQUENT REPORT	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
Date of Work Completion: 5/1/2015			
	OPERATOR CHANGE	PLUG AND ABANDON	L PLUG BACK
SPUD REPORT Date of Spud:	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
	☐ WILDCAT WELL DETERMINATION ✓	OTHER	OTHER: See Below
12. DESCRIBE PROPOSED OR	COMPLETED OPERATIONS. Clearly show all p	pertinent details including dates, d	lepths, volumes, etc.
	wnsize, deepen, & convert to d		
			Accepted by the Utah Division of
			Oil, Gas and Mining
			FOR RECORD ONLY
			June 18, 2015
NAME (PLEASE PRINT)	PHONE NUMBER	TITLE	
Maria S. Gomez	713 997-5038	Principal Regulatory Analys	it
SIGNATURE N/A		<b>DATE</b> 6/16/2015	
14/73		U/ 1U/ LU 1U	

## **CENTRAL DIVISION**

ALTAMONT FIELD THORNE 3-31B4 THORNE 3-31B4 WORKOVER LAND

# **Operation Summary Report**

Disclaimer: Although the information contained in this report is based on sound engineering practices, the copyright owner (s) does (do) not accept any responsibility whatsoever, in negligence or otherwise, for any loss or damage arising from the possession or use of the report whether in terms of correctness or otherwise. The application, therefore, by the user of this report or any part thereof, is solely at the user's own risk.

**CENTRAL DIVISION** 

#### 1 General

#### **Customer Information** 1.1

Company	CENTRAL DIVISION
Representative	
Address	

#### 1.2 **Well Information**

Well	THORNE 3-31B4							
Project	ALTAMONT FIELD	Site	THORNE 3-31B4					
Rig Name/No.		Event	WORKOVER LAND					
Start date	4/27/2015	End date	5/2/2015					
Spud Date/Time	8/30/2013	UWI	THORNE 3-31B4					
Active datum	KB @6,068.3ft (above Mean Sea Level)	·						
Afe	164495/53676 / THORNE 3-31B4							
No./Description								

#### 2 Summary

#### 2.1 **Operation Summary**

Date		Time art-End	Duratio n (hr)	Phase	Activit	Sub	OP Code	MD from (ft)	Operation
4/28/2015	6:00	7:00	1.00	MIRU	28		Р		CREW TRAVEL TO LOCATION HSM WRITE AND REVIEW JSA TOPIC; MOVING RIG
	7:00	9:30	2.50	MIRU	01		Р		RAOD RIG FROM THE 8-20C4 TO LOCATION SLIDE ROTO FLEX MIRU PUMP 60 BBLS OF HOT 2% KCL WATER DOWN ANNULAS
	9:30	12:00	2.50	PRDHEQ	39		Р		L/D POLISH ROD ATTEMPT TO WORK PUMP OFF SEAT FAILED PULL ROD STUCK R/U BACK OFF TOOL BACK OFF RODS
	12:00	14:00	2.00	PRDHEQ	39		Р		TOH L/D 103-1" RODS 20-7/8" RODS
	14:00	14:45	0.75	WLWORK	21		Р		HSM UPDATE JSA TOPIC; WIRELINE OPERATIONSMIRU WIRELINE TIH PERFORATE TBG AT 3067' TOH R/D WIRELINE FLUSH TBG w 20 BBLS OF 2% KCL WATER
	14:45	15:37	0.87	WOR	16		Р		HSM UPDATE JSA TOPIC; N/D N/U BOPE; N/D WELL HEAD N/U BOPE RELEASE 7" TAC
	15:37	18:30	2.88	PRDHEQ	39		Р		TOH w 96-JTS OF 2 7/8" TBG TO THE TOP OF RODS MAKE BACK OFF CONTINUE L/D RODS 27-7/8" RODS SECURE WELL TIW VALVE w NIGHT CAP BOPE CLOSED AND LOCKED 7 CSG VALVE OPEN TO SALES
4/29/2015	6:00	7:00	1.00	WOR	28		Р		CREW TRAVEL TO LOCAITON HSM WRITE AND REVIEW JSA TOPIC; STRIPPING PRODUCTION
	7:00	16:00	9.00	WOR	39		Р		CONTINUE STRIPPING PRODUCTION TTL OF 265-JTS OF 2 7/8" TBG TTL OF 103-1" RODS 111-7/8" RODS 117-3/4" RODS 17-1 1/2" K BARS L/D BHA CLEAN WORK AREA
	16:00	17:00	1.00	SL	32		Р		P/U 1" JT OF 2 7/8" TBG MIRU SLICK LINE TRUCK PBTD 12464' TIH TAG AT 12453' SLMD TOH R/D SLICK LINE TRUCK
	17:00	18:30	1.50	PRDHEQ	39		Р		P/U 5 3/4" OPEN NO-GO TIH w 205 JTS OF 2 7/8" TBG SECURE WELL TIW VALVE w NIGHT CAP CLOSE PIPE RAMS AND LOCK 7" CSG OPEN TO SALES SDFN EOT 6692'
4/30/2015	6:00	7:00	1.00	PRDHEQ	28		Р		CREW TRAVEL TO LOCATION HSM WRITE AND REVIEW JSA TOPIC; TRIPPING TBG
	7:00	7:40	0.67	PRDHEQ	39		Р		CSIP 100 PSI TSIP 100 PSI BLEED WELL OFF FINISH TIH w 60-JTS OF 2 7/8" TBG
	7:40	8:30	0.83	PRDHEQ	06		Р		FLUSH TBG w 60 BBLS OF HOT 2% KCL WATER
	8:30	13:30	5.00	PRDHEQ	39		Р		MIRU SCANNING EQUIPMENT SCAN 267-JTS OF 2 7/8" TBG L/D 69 RED 25 BLUE STAND BACK 173 YELLOW BAND RDMO SCANNING EQUIPMENT

**CENTRAL DIVISION** 

#### 2.1 **Operation Summary (Continued)**

Date		Time art-End	Duratio n (hr)	Phase	Activit y	Sub	OP Code	MD from (ft)	Operation
	13:30	18:30	5.00	PRDHEQ	39		Р		TALLY AND P/U 2 3/8" BULL PLUG 2-JTS OF 2 3/8" TBG 2303 DE-SANDER 2' TBG SUB 2 3/8" PSN 4-JTS OF 2 3/8" TBG 5" TAC 45-JTS OF 2 3/8" TBG CHANGE HANDLING TOOLS R/U HYDROTEST TOOLS TALLY AND TEST 173-JTS OF 2 7/8" YELLOW BAND TBG R/D HYDROTEST TOOLS SECURE WELL TIW VALVE W NIGHT CAP CLOSE PIPE RAMS AND LOCK 7" CSG OPEN TO SALES SDFN EOT 7324'
5/1/2015	6:00	7:00	1.00	PRDHEQ	28		Р		CREW TRAVEL TO LOCATION HSM WRITE AND REVIEW JSA TOPIC; PICKING UP TBG & HAND PLACEMENT
	7:00	11:00	4.00	PRDHEQ	39		Р		CSIP 100 PSI TSIP 100 PSI BLEED OFF WELL CONTINUE TIH TALLY & P/U 115-JTS OF NEW 2 7/8" TBG SET 5" TAC AT 10864' PSN AT 10994' EOT 11081' LAND TBG R/D FLOOR N/D BOPE REMOVE LANDING SUB INSTALL B-FLANGE LAND TAC IN TENTION 20K N/U WELL HEAD SECURE WELL W VALVE AND NIGHT CAP IN TBG 7" CSG OPEN TO SALES
	11:00	12:00	1.00	RDMO	02		Р		RDMO
	12:00	15:00	3.00	INARTLT	03		N		WAIT ON CO-ROD UNIT TO FINISH INSTALL ON THE MOON 3-30C4
	15:00	19:00	4.00	INARTLT	03		Р		HSM WRITE AND REVIEW JSA TOPIC; CO-ROD OPERATIONS MIRU CO-ROD UNIT P/U 2" X 1 1/2" X 38' 60 RING PA PUMP TIH W 1ST REAL OF CO-ROD 7800' WELD ROD SECURE WELL CLOSE CO-ROD BOPE CLOSE TOP AND BTM RADIGANS WELL OPEN TO SALES SDFN
5/2/2015	6:00	7:00	1.00	PRDHEQ	28		Р		CREW TRAVEL TO LOCATION HSM WRITE AND REVIEW JSA TOPIC; CO-ROD OPERATIONS
	7:00	10:39	3.65	PRDHEQ	39		Р		CSIP 100 TSIP 100 BLEED OFF WELL CONTINUE TIH w CO-ROD SPACE OUT CUT AND WELD PIN SPACE w 2' 4' 6' 8' X 1" PONY ROD FILL TBG w 35 BBLS OF 2% KCL TEST AND STROKE TEST TO 1000 PSI GOOD
	10:39	12:30	1.85	PRDHEQ	39		Р		RDMO SLIDE UNIT TURN WELL OVER TO PRODUCTION

#### **CENTRAL DIVISION**

## **Table of Contents**

1	General
1.1	Customer Information
1.2	Well Information
2	Summary
2.1	Operation Summary


	STATE OF UTAH		FORM 9
	DEPARTMENT OF NATURAL RESOURC		5.LEASE DESIGNATION AND SERIAL NUMBER:
	DIVISION OF OIL, GAS, AND MIN	ING	Fee
SUNDF	RY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for pro current bottom-hole depth, FOR PERMIT TO DRILL form	7.UNIT or CA AGREEMENT NAME:		
1. TYPE OF WELL Oil Well			8. WELL NAME and NUMBER: Thorne 3-31B4
2. NAME OF OPERATOR: EP ENERGY E&P COMPANY,	9. API NUMBER: 43013520860000		
3. ADDRESS OF OPERATOR: 1001 Louisiana, Houston,	TX, 77002 713 997-50	PHONE NUMBER: 038 Ext	9. FIELD and POOL or WILDCAT: ALTAMONT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0900 FSL 1400 FEL			COUNTY: DUCHESNE
QTR/QTR, SECTION, TOWNSI Qtr/Qtr: SWSE Section: 3	HIP, RANGE, MERIDIAN: 31 Township: 02.0S Range: 04.0W Meric	lian: U	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICAT	E NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
7	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
10/27/2015	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
Date of Work Completion:	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	✓ RECOMPLETE DIFFERENT FORMATION
SPUD REPORT Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
Report Date:	WILDCAT WELL DETERMINATION	OTHER	OTHER:
40 DECORIDE PROPOSED OR	COMPLETED OPERATIONS. Clearly show a	U martinant datalla includina datas	deaths well-man at
	plete to the Wasatch/LGR. So		Approved by the Wetoberisi@n2015 Oil, Gas and Mining
			Date:
			By: Dar K Quit
NAME (PLEASE PRINT)	PHONE NUMB		
Maria S. Gomez	713 997-5038	Principal Regulatory Analys	st ————————————————————————————————————
SIGNATURE N/A		<b>DATE</b> 10/19/2015	

# Thorne 3-31B4 Recom Summary Procedure

- POOH with rods, pump & tubing. Inspect/Repair/Re-furbish as needed. Replace any bad tubing and joints of rods.
- Set two CBPs for 5" 18# casing @ 9,863' & 9,845' to plug back currently producing zones (Top perf @ 9,869'). Dump bail 30' sand on top of plug @ 9,845'.
- Stage 1:
  - o Perforate new LGR interval from 9,552' 9,806'.
  - Prop Frac Perforations with 120,000 lbs 30/50 prop (w/ 3,000 lbs 100 mesh & 5,000 gals 15% HCl acid) (Stage 1 Recom).
- Stage 2:
  - o RIH with 7" CBP & set @ 9,473'.
  - o Perforate new LGR interval from 9,230' 9,458'.
  - Prop Frac Perforations with 110,000 lbs 30/50 prop (w/ 3,000 lbs 100 mesh & 5,000 gals 15% HCl acid) (Stage 2 Recom).
- Stage 3:
  - o RIH w/ 7" CBP & set @ 9,161'.
  - o Perforate new LGR interval from 8,850' 9,146'.
  - o Acidize perforations with w/ 26,500 Gals 15% HCl Acid (STAGE 3 Recom)
- Clean out well drilling up (2) 7" CBP's to ~9,830', leaving ~15' sand on top of 5" CBP @ 9,845' (5" plug @ 9,863' will remain, also). Top perf BELOW plug @ 9,869'.
- RIH w/ production tubing and rods.
- Clean location and resume production.




#### **Current D&D+COROD Pumping Schematic**





#### **Proposed RECOM Pumping Schematic**



	STATE OF UTAH		FORM 9
	DEPARTMENT OF NATURAL RESOURCE DIVISION OF OIL, GAS, AND MIN		5.LEASE DESIGNATION AND SERIAL NUMBER:
		IIING	Fee
	RY NOTICES AND REPORTS		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	oposals to drill new wells, significantly or reenter plugged wells, or to drill horizon n for such proposals.		7.UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well			8. WELL NAME and NUMBER: Thorne 3-31B4
2. NAME OF OPERATOR: EP ENERGY E&P COMPANY,	LP.		9. API NUMBER: 43013520860000
3. ADDRESS OF OPERATOR: 1001 Louisiana , Houston,	TX, 77002 713 997-50	PHONE NUMBER: 038 Ext	9. FIELD and POOL or WILDCAT: ALTAMONT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0900 FSL 1400 FEL			COUNTY: DUCHESNE
QTR/QTR, SECTION, TOWNS	HIP, RANGE, MERIDIAN: 31 Township: 02.0S Range: 04.0W Merio	dian: U	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICAT	E NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
1/18/2016	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
Date of Work Completion:	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
SPUD REPORT Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
	TUBING REPAIR	VENT OR FLARE	☐ WATER DISPOSAL ☐
DRILLING REPORT Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
	WILDCAT WELL DETERMINATION	<b>✓</b> OTHER	OTHER: Drill Out
	COMPLETED OPERATIONS. Clearly show a put CBP's @ 9850' & 9840' w.		depths, volumes, etc.  Approved by the  Ulamu Biyis G, n2016  Oil, Gas and Mining  Date:
			By: Dork Dunt
NAME (PLEASE PRINT)	PHONE NUMB		
Maria S. Gomez	713 997-5038	Principal Regulatory Analys	st
SIGNATURE N/A		<b>DATE</b> 1/13/2016	

				RTMEN	TATE ( T OF N/ F OIL,	ATURA	L RESC		3 —	COM	PLETION	(hi	ighlight cl	REPORT   hanges)	FORM 8
WELI	L CON	/IPLE	TION	OR I	RECC	MPL	ETIC	N RI	EPOR	T ANI	D LOG	6. I	F INDIAN, A	ALLOTTEE OR TRI	BE NAME
1a. TYPE OF WELL:	:	(	OIL C	]	GAS C		DRY		OTHE	R		7. l	JNIT or CA	AGREEMENT NAM	E
b. TYPE OF WORK	(: HORIZ. LATS.	7 :	DEEP-	٦	RE- ENTRY	7	DIFF. RESVR.		OTHE	D		8. \	WELL NAME	and NUMBER:	
2. NAME OF OPERA			IN L		LINTIK! L		NLOVK.		OTTL			9. /	API NUMBEI	R:	
3. ADDRESS OF OP	PERATOR:		CITY			STATE	:	ZIP		PHONE	NUMBER:	10 F	FIELD AND I	POOL, OR WILDC	AT
4. LOCATION OF W AT SURFACE:	ELL (FOOT		0111			OTATE	•	211		1		11.	QTR/QTR, MERIDIAN:	SECTION, TOWNS	SHIP, RANGE,
AT TOP PRODUC	CING INTER	RVAL REPO	ORTED BE	ELOW:										1	
AT TOTAL DEPT	H:											12.	COUNTY	1	3. STATE UTAH
14. DATE SPUDDED	D:	15. DATE	T.D. REA	CHED:	16. DAT	E COMPL	ETED:	,	ABANDONE	D 🔲	READY TO PRODU	JCE	17. ELEV	ATIONS (DF, RKB	RT, GL):
18. TOTAL DEPTH:	MD TVD			19. PLUG	BACK T.E	D.: MD TVD			20. IF M	ULTIPLE C	OMPLETIONS, HOV	V MANY? *		TH BRIDGE MD JG SET:	ı
22. TYPE ELECTRIC	C AND OTH	ER MECHA	NICAL LC	OGS RUN	Submit cop	oy of each	)			WAS DST	LL CORED? RUN? DNAL SURVEY?	NO NO	· 🖺 YI	ES (Subr	nit analysis) nit report) nit copy)
24. CASING AND LI	NER RECO	RD (Repor	t all strinç	js set in w	rell)		ī		Ī		<u> </u>		ı		1
HOLE SIZE	SIZE/GI	RADE	WEIGH	T (#/ft.)	TOP	MD)	вотто	OM (MD)	DEF	EMENTER PTH	CEMENT TYPE & NO. OF SACKS		JRRY ME (BBL)	CEMENT TOP **	AMOUNT PULLE
25. TUBING RECOR	RD														
SIZE	DEPTH	SET (MD)	PAC	KER SET (	MD)	SIZE		DEPTH	SET (MD)	PACKE	R SET (MD)	SIZE	DE	EPTH SET (MD)	PACKER SET (MD)
26. PRODUCING IN	TERVALS		_!						:	7. PERFO	RATION RECORD				
FORMATION	NAME	TO	P (MD)	BOTT	OM (MD)	TOP	(TVD)	вотто	M (TVD)	INTERVA	AL (Top/Bot - MD)	SIZE	NO. HOLE	ES PERFOR	ATION STATUS
(A)														Open	Squeezed
(B)														Open	Squeezed
(C)														Open	Squeezed
(D)														Open	Squeezed
28. ACID, FRACTUR	RE, TREATM	MENT, CEN	IENT SQL	JEEZE, ET	c.										
DEPTH I	NTERVAL								AMO	UNT AND 1	TYPE OF MATERIAL	-			
														_	
29. ENCLOSED ATT	TACHMENT	s: CBF	P's 98	350 &	9840	with	30' s	and o	on top	_		_			L STATUS:
=	RICAL/MEC			O CEMEN	Γ VERIFICA	ATION	$\equiv$	GEOLOG CORE AN	C REPORT ALYSIS		DST REPORT OTHER:	DIREC	CTIONAL SU	JRVEY	

(CONTINUED ON BACK)

31. INITIAL PRO	ODUCTION				INT	ERVAL A (As sho	wn in item #26)						
DATE FIRST PR	ODUCED:	TEST DA	TE:		HOURS TESTER	D:	TEST PRODUCTION RATES: →	N	OIL – BBL:	GAS – MCF:	WATER -	- BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PR	ESS. API GR	AVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →		OIL – BBL:	GAS – MCF:	WATER -	- BBL:	INTERVAL STATUS:
			<u> </u>		INT	ERVAL B (As sho	wn in item #26)			<u>'</u>			•
DATE FIRST PR	ODUCED:	TEST DA	TE:		HOURS TESTER	D:	TEST PRODUCTION RATES: →	N	OIL – BBL:	GAS - MCF:	WATER -	- BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PR	ESS. API GR	AVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTIC RATES: →	NC	OIL – BBL:	GAS - MCF:	WATER -	- BBL:	INTERVAL STATUS:
					INT	ERVAL C (As sho	wn in item #26)						
DATE FIRST PR	ODUCED:	TEST DA	TE:		HOURS TESTER	TEST PRODUCTION RATES: →	Ŋ	OIL – BBL:	GAS – MCF:	WATER -	- BBL:	PROD. METHOD:	
CHOKE SIZE:	TBG. PRESS.	CSG. PR	ESS. API GR	SS. API GRAVITY BTU – GAS			24 HR PRODUCTIC RATES: →	NC	OIL – BBL:	GAS – MCF:	WATER -	- BBL:	INTERVAL STATUS:
		I.	l .		INT	ERVAL D (As sho	wn in item #26)						•
DATE FIRST PR	ODUCED:	TEST DA	TE:		HOURS TESTER	D:	TEST PRODUCTION RATES: →	N	OIL – BBL:	GAS - MCF:	WATER -	- BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PR	ESS. API GR	AVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	NC	OIL – BBL:	GAS – MCF:	WATER -	- BBL:	INTERVAL STATUS:
32. DISPOSITIO	ON OF GAS (So	d, Used for F	uel, Vented, Etc	:.)	I				I.	•			•
33. SUMMARY	OF POROUS Z	ONES (Includ	e Aquifers):					34.	. FORMATION	(Log) MARKERS:			
			ents thereof: Core nd shut-in pressu			n tests, including de	epth interval						
Formation	on	Top (MD)	Bottom (MD)		Descrip	otions, Contents, etc	<b>:</b> .			Name		(1	Top Measured Depth)
35. ADDITIONA	L REMARKS (I	nclude pluggi	ing procedure)	-			-				•		
36. I hereby cer	rtify that the for	egoing and a	ttached informa	ition is c	omplete and corr	ect as determined	from all available re	cor	rds.				
NAME (PLEAS	SE PRINT)						TITLE						
SIGNATURE							DATE						

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining

1594 West North Temple, Suite 1210

Box 145801

Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

(5/2000)

<sup>\*</sup> ITEM 20: Show the number of completions if production is measured separately from two or more formations.

**CENTRAL DIVISION** 

#### 1 General

#### 1.1 Customer Information

Company	CENTRAL DIVISION
Representative	
Address	

#### 1.2 Well Information

Well	THORNE 3-31B4							
Project	ALTAMONT FIELD	Site	THORNE 3-31B4					
Rig Name/No.		Event	RECOMPLETE LAND					
Start date	10/28/2015	End date	11/13/2015					
Spud Date/Time	8/30/2013	UWI	THORNE 3-31B4					
Active datum	KB @6,068.3ft (above Mean Sea Level)	·						
Afe	165541/54983 / THORNE 3-31B4							
No./Description								

## 2 Summary

## 2.1 Operation Summary

Date		Γime art-End	Duratio n (hr)	Phase	Activit y	Sub	OP Code	MD from (ft)	Operation
10/30/2015	6:00	7:30	1.50	WOR	28		Р		CREW TRAVEL HELD SAFETY MEETING ON TOOH W/ CO-ROD. FILLED OUT AND REVIEWED JSA.
	7:30	10:00	2.50	WOR	06		Р		PUMPED 60 BBLS DOWN CSG. LD POLISH ROD. WORKED PUMP OFF SEAT. FLUSHED TBG 65 BBLS.
	10:00	13:30	3.50	WOR	39		Р		TOOH W/ CO-ROD STRING AND PUMP. WHILE PUMPING 40 BBLS DOWN TBG TO KEEP CO-ROD CLEAN. RD CO-ROD RIG
	13:30	14:30	1.00	MIRU	01		Р		MIRU SERVICE RIG.
	14:30	16:00	1.50	WOR	16		Р		ND WELLHEAD AND B-FLANGE. INSTALLED 4' PERF SUB, 2' SUB HANGER AND DOUBLE CHECK VALVE. NU AND PRESSURE TEST 5K BOP.
	16:00	17:30	1.50	WOR	39		Р		RELEASED TAC. RU SCANNERS. SOOH SCANNING TBG. TOOH W/ 120-JTS 2 7/8 L-80 EUE TBG ALL YELLOW. EOT @ 7192'. CLOSED IN WELL. CLOSED AND LOCKED PIPE RAMS.CLOSED CSG VALVES AND INSTALLED NIGHT CAPS. CLOSED TIW VALVE AND INTALLED NIGHT CAP. SDFN.
10/31/2015	6:00	7:30	1.50	WOR	28		Р		CREW TRAVEL HELD SAFETY MEETING ON SCANNING TUBING. FILLED OUT AND REVIEWED JSA.
	7:30	10:30	3.00	WOR	39		Р		0 TSIP 0 CSIP. OPENED WELL. CONTINUED SCANNING TBG. SCANNED168-JTS 2 7/8 L-80 EUE TBG ( TTL 282 YELLOW, 5-BLUE AND 1-RED). RD SCANNERS LD 45-JTS 2 3/8 L-80 EUE TBG, TAC, 4-JTS 2 3/8 L-80 EUE TBG AND BHA.
	10:30	14:00	3.50	WLWORK	26		Р		RU WIRELINE PRESSURE TEST LUBRICATOR. RIH W/ 4.0 GR/JB. TAGGED @ 9861'. TRIED TO WORK DOWN GOT STUCK. KEPT WORKING GR/JB GOT IT TO GO DOWN FREE BUT NOT UP KEPT TAGGING 9861'. WHILE WORKING GR/JB PULLED OUT OF CABLE HEAD. POOH. RD WIRELINE.
	14:00	16:30	2.50	WOR	42		N		WAIT ON TUBING AND OVERSHOT
	16:30	19:00	2.50	WOR	52		Р		TALLIED AND RIH W/ 3 3/4 OVERSHAOT W/ 2 3/4 OVERSHOT, 3' EXTENSION, TOP SUB, 98- JTS 2 3/8 L-80 EUE TBG, X-OVER AND 22-JTS 2 7/8 L-80 EUE TBG. EOT @ 3941',CLOSED IN WELL. CLOSED AND LOCKED PIPE RAMS.CLOSED CSG VALVES AND INSTALLED NIGHT CAPS. CLOSED TIW VALVE AND INTALLED NIGHT CAP. SDFN.

11/1/2015

**CENTRAL DIVISION** 

#### 2.1 **Operation Summary (Continued)**

Date		Γime ırt-End	Duratio n (hr)	Phase	Activit y	Sub	OP Code	MD from (ft)	Operation
	6:00	7:30	1.50	WOR	28		Р		CREW TRAVEL HELD SAFETY MEETING ON TRIPPING TUBING FILLED OUT AND REVIEWED JSA
	7:30	17:30	10.00	WOR	52		P		50 TSIP, 50 CSIP. BLED DOWN WELL. CONTINUED RIH W/ 184-JTS 2 7/8 L-80 EUE TBG. TAGGED @ 9861' PUSHING DOWN THRU IT @ 5,000 OVER. PULIING THRU IT @ 5,000 OVER WORKED THRU IT FEW TIMES. CONTINUED RIH TAGGED @ 12446' SET DOWN PULLED 20,000 OVER TO GET FREE. TOOH W/ 78-JTS 2 7/8 EUE TBG. PULLED THRU TIGHT SPOT @ 9861'@ 2000 OVER. CONTINUED TOOH W/ 206 JTS 2 7/8 L-80 EUE TBG, X-OVER, 99-JTS 2 3/8 L-80 EUE TBG, OVER SHOT, AND CCL GR/JB. RIH W/ 98-JTS 2 3/8 L-80 EUE TBG. LD 98-JTS 2 3/8 TBG. CLOSED IN WELL. CLOSED AND LOCKED BLIND RAMS.CLOSED CSG VALVES AND INSTALLED NIGHT CAPS. CLOSED TIW VALVE AND INSTALLED NIGHT CAP. SDFN.
11/2/2015	6:00	7:30	1.50	WOR	28		Р		CREW TRAVEL HELD SAFETY MEETING ON WIRELINE SAFETY FILLED OUT AND REVIEWED JSA.
	7:30	14:00	6.50	WLWORK	26		P		0 CSIP. RU WIRELINE SET CBP @ 9850' FILLED CSG W/ 240 BBLS PRESSURE TEST @ 2000 PSI HELD. RIH PRESSURED TO 2000 PSI SET SECOND CBP @ 9840', RIH W/ 6.00 GRJB TO LINER TOP @ 9504' MADE 2 RUNS DUMPED BAILED 30' SAND. RD WIRELINE
	14:00	17:00	3.00	WOR	16		Р		ND BOP NU FRAC VALVE. PRESSURE TEST CSG @ 8000 PSI HELD, NU 2 HCR VALVES AND GOAT HEAD. CLOSED IN WELL CLOSED FRAC VALVES. CLOSED CSG VALVE AND INSTALLED NIGHT CAPS.
11/3/2015	6:00	7:30	1.50	WOR	28		Р		CREW TRAVEL HELD SAFETY MEETING ON PRESSURE TESTING. FILLED OUT AND REVIEWED JSA.
	7:30	8:30	1.00	WHDTRE	18		Р		PRESSURE TEST FRAC STACK @ 9500 PSI HELD.
	8:30	11:00	2.50	WLWORK	21		P		MIRU WIRELINE PERFORATED STAGE #1 FROM 9806' TO 9552'. ALL PERFS CORRELATED TO THE PERFORATORS SECTOR CBL GAMMA RAY CCL LOG RUN #1 DATED 10/4/2013. 22 NET FT. 66 SHOTS. USING 2 3/4" GUNS, 16 GM CHARGES, 3 SPF, 120 PHASING. STARTING PRESSURE 1000 PSI. FINAL PRESSURE 300 PSI. CLOSED IN WELL. CLOSED AND LOCKED FRAC VALVES. CLOSED CSG VALVE AND INSTALLED NIGHT CAPS. SDFN.
11/4/2015	6:00	7:30	1.50	WOR	28		Р		CREW TRAVEL HELD SAFETY MEETING ON RIGGING UP FRAC EQUIPMENT. FILLED OUT AND REVIEWED JSA.
	7:30	18:00	10.50	MIRU	01		Р		FRAC CREW COULDN'T MAKE IT. SENT RIG CREW HOME. FRAC SPOTTE IN 6 PUMP TRUCKS, DATA VAN AND CHEMICAL TRAILER. SDFN.
11/5/2015	6:00	6:30	0.50	MIRU	28		Р		HELD SAFETY MEETING ON RIGGING UP FRAC EQUIPMENT. FILLED OUT AND REVIEWED JSA.
	6:30	10:30	4.00	MIRU	01		Р		MIRU C&J FRAC EQUIPMENT. LINES NOT UP TO DATE ON INSPECTION.
	10:30	20:00	9.50	MIRU	01		Р		WAIT FOR AND INSTALL DIFFERENT HARD LINE. SDFN.
11/6/2015	6:00	7:30	1.50	WOR	28		Р		CREW TRAVEL HELD SAFETY MEETING ON PUMPING PRESSURE. FILLED OUT AND REVIEWED JSA
	7:30	12:30	5.00	SITEPRE	42		N		FINISHED RIGGING UP FRAC EQUIPMENT. WAIT ON BOSQUE COL2 UNIT TREATED TANKS

## 2.1 Operation Summary (Continued)

Date		ime	Duratio	Phase	Activit	Sub	OP	MD from	Operation
	Sta	rt-End	n (hr)		У		Code	(ft)	
	12:30	14:00	1.50	STG01	35		Р		PRESSURE TEST LINES @ 9500 PSI. OPENED UP WELL W/ 150 PSI. BREAK DOWN STAGE # 1 PERFS @ 4162 PSI, 9.8 BPM, 13 BBLS PUMPED. EST INJ RATE 31.7 BPM, 4729 PSI. STEP RATE TEST 36 OPEN PERFS. I.S.I.P. 3414 PSI. F.G79, 5 MIN 2972 PSI, 10 MIN 2860 PSI. TREATED PERFS W/ 5000 GALS 15% HCL ACID. PUMPED 3000 LBS 100 MESH IN 1/2 PPG STAGE AND 117913 LBS WHITE 30/50. IN .5#, 1#, 1.5#, 2# AND 3# STAGES. AVG RATE 68 BPM, MAX RATE 69 BPM. AVG PRESS 4979, MAX PRESS 7068. I.S.I.P. 3097 PSI. F.G753. 5 MIN 2963 PSI, 10 MIN 2924 PSI. SHUT WELL IN 3649 BBLS TO RECOVER. TURNED WELL OVER TO WIRELINE
	14:00	16:30	2.50	STG02	21		Р		RU WIRELINE PERFORATED STAGE #2 FROM 9458' TO 9230'. ALL PERFS CORRELATED TO THE PERFORATORS SECTOR CBL GAMMA RAY CCL LOG RUN #1 DATED 10/4/2013. 23 NET FT. 69 SHOTS. USING 3 1/8" GUNS, 22.7 GM CHARGES, 3 SPF, 120 PHASING. STARTING PRESSURE 2600 PSI. FINAL PRESSURE 1200 PSI. TURNED WELL OVER TO FRAC CREW.
	16:30	19:00	2.50	STG02	35		N		PRESSURE TEST LINES @ 9430 PSI. OPENED UP WELL W/ 1345 PSI. BREAK DOWN STAGE # 2 PERFS @ 1923 PSI, 7.3 BPM, 8 BBLS PUMPED. EST INJ RATE 31.1 BPM, 2219 PSI. STEP RATE TEST ALL PERFS OPEN. I.S.I.P. 1410 PSI. F.G58, 5 MIN 1216 PSI, 10 MIN 1165 PSI. TREATED PERFS W/ 5000 GALS 15% HCL ACID. PUMPED 3000 LBS 100 MESH IN 1/2 PPG STAGE AND 3538. LBS WHITE 30/50. IN .5#. BELT ON SAND MASTER QUIT WORKING FLUSHED WELL TO BTM PERF. AVG RATE 66 BPM, MAX RATE 72 BPM. AVG PRESS 2429, MAX PRESS 3057. I.S.I.P. 1549 PSI. F.G599, 5 MIN 1481 PSI, 10 MIN 1427PSI. SHUT IN WELL WORKED ON SAND MASTER. THINK KEY WAY ON BELT DRIVE, SHEARED. SDFN.
11/7/2015	6:00	7:30	1.50	WOR	28		Р		CREW TRAVEL HELD SAFETY MEETING ON ICE PLUGS FILLED OUT AND REVIEWED JSA.
	7:30	10:00	2.50	WOR	42		Р		WAIT ON FRAC CREW
	10:00	11:30	1.50	STG02	35		Р		PRESSURE TEST LINES @ 9575 OPENED W/ 814 PSI.PUMPED 3000 LBS WHITE 30/50 IN 1/2 PPG STAGE. PUMP CROSSLINK PAD THEN PUMPED 105,709 LBS WHITE 30/50. IN .5#, 1#, 1.5#, 2# AND 3# STAGES. AVG RATE 69 BPM, MAX RATE 71 BPM. AVG PRESS 2676, MAX PRESS 3848. I.S.I.P. 1909 PSI. F.G637. 5 MIN 1803 PSI, 10 MIN 1734 PSI. SHUT WELL IN 2985 BBLS TO RECOVER. TURNED WELL OVER TO WIRELINE
	11:30	13:30	2.00	STG03	21		Р		RU WIRELINE SET CBP @ 9170' W/ 1400 PSI. PERFORATED STAGE #3 FROM 9146' TO 8850'. ALL PERFS CORRELATED TO THE PERFORATORS SECTOR CBL GAMMA RAY CCL LOG RUN #1 DATED 10/4/2013. 23 NET FT. 69 SHOTS. USING 3 1/8" GUNS, 22.7 GM CHARGES, 3 SPF, 120 PHASING. STARTING PRESSURE 1400 PSI. FINAL PRESSURE 1350 PSI. TURNED WELL OVER TO FRAC CREW.
	13:30	14:30	1.00	STG03	35		P		PRESSURE TEST LINES @ 8879. OPENED WELL W/ 1328 PSI. BREAK DOWN STAGE #3 PERFS @ 2990 PSI, 29 BPM, 20 BBLS PUMPED. EST INJECTION RATE 31 BPM 2209 PSI. I.S.I.P. 1530 PSI F.G609. TREATED PERFS W/ 13250 GALS 15% HCL ACID.DROPPED 95 BIO BALLS. THEN PUMPED 13250 GAL 15% HCL. AVG RATE 45.3 BPM, MAX RATE 50.1 BPM. AVG PRESS 2511 PSI, MAX PRESS 7645 PSI. I.S.I.P. 1588 PSI, F.G609, SHUT IN WELL. 1226 BBLS TO RECOVER STARTED RIGGING DOWN FRAC EQUIPMENT.
	14:30	17:30	3.00	RDMO	02		P		RD FRAC EQUIPMENT.
	17:30	19:30	2.00	WOR	18		Р		WAIT TO OPEN WELL

**CENTRAL DIVISION** 

#### 2.1 **Operation Summary (Continued)**

Date		Time	Duratio	Phase	Activit	Sub	ОР	MD from	Operation
	Sta	art-End	(hr)		У		Code	(ft)	
	19:30	6:00	10.50	STG02	19		Р		OPEN WELL @ 7:30 1150 ON 12 CHOKE.
									725 PSI. 14 CHOKE, RECOVERED 0 BBLS OIL, 408 BBLS H20 AND 0 MCF.
11/8/2015	6:00	7:30	1.50	WOR	28		Р		CREW TRAVEL HELD SAFETY MEETING ON ND FRAC VALVES. FILLED OUT AND REVIEWED JSA.
	7:30	10:00	2.50	WOR	16		Р		WELL STILL FLOWING ND TOP HCR VALVE AND GOAT HEAD. RAN FLOWLINE TO TREATER,
	10:00	6:00	20.00	WOR	19		Р		400 PSI ON 16 CHOKE. RECOVERED 0 MCF, 0 BBLS OIL, AND 944 BBLS H2O.
11/9/2015	6:00	7:30	1.50	FB	28		Р		HELD SAFETY MEETING ON FLOWBACK PROCEDURE. FILLED OUT AND REVIEWED JSA.
	7:30	6:00	22.50	FB	19		Р		250 PSI ON 16 CHOKE. RECOVERED 0 MCF, 0 BBLS OIL, AND 573 BBLS H2O.
11/10/2015	6:00	7:30	1.50	CTU	28		Р		CREW TRAVEL HELD SAFETY MEETING ON RIGGING UP COIL TUBING. FILLED OUT AND REVIEWED JSA
	7:30	10:30	3.00	MIRU	01		Р		MIRU 2" COIL TUBING. MU BHA W/ 6" BLADED INSERT MILL PRESSURE TEST LUBE AND FLOW BACK LINE @ 8500 PSI HELD.
	10:30	23:00	12.50	СТИ	10		P		RIH PUMPING 1 BPM AND RETURNING 1 BPM. TO 8500'. INCRESED RATE TO 3 BPM AND RETURN 3 1/2 BPM @ 200 PSI. DRILLOUT CBPS sET @ 9170' AND 9473' CHASED CBP TO LINER TOP. @ 9504' TOOH W/ COIL TBG AND 6" MILL. RIH W/ BHA AND 4 1/8" JZ ROCK BIT. FINISHED DRILLING CBP @ LT @ 9504' CLEANED OUT TO PBTD @ 9820', CICULATE CLEAN FOR 1 HR. TOOH W/ COIL TBG @ 4 1/8 BIT. BUMPED UP.
	23:00	1:00	2.00	CTU	02		Р		LD BHA, BLEW COIL TUBING DRY. FINISNHED RD COIL TUBING OPENED WELL ON 12 CHOKE W/ 150 PSI.
	1:00	6:00	5.00	FB	19		Р		250 PSI ON 14 CHOKE. RECOVERED 0 MCF, 0 BBLS OIL, AND 105 BBLS H2O.
11/11/2015	6:00	6:30	0.50	FB	28		Р		HELLD SAFETY MEETING ON FLOWBACK PROCEDURES. FILLED OUT AND REVIEWED JSA.
	6:30	6:00	23.50	FB	19		Р		50 PSI ON 48/48 CHOKE. RECOVERED 0 MCF, 0 BBLS OIL, AND 598 BBLS H2O.
11/12/2015	6:00	7:30	1.50	WOR	28		Р		CREW TRAVEL HELD SAFETY MEETING ON WELL CONTROL. FILLED OUT AND REVIEWED JSA.
	7:30	9:30	2.00	WOR	15		Р		OPENED WELL THRU 2" VALVE TO FLOW BACK TANK. FLOWING A LITTE WATER. PUMPED 200 BBLS BRINE @ 5 BPM @ 800 PSI. ISIP 200 PSI. SHUT IN WELL FOR 1/2 HOUR PRESSURE DROPPED TO 0 PSI. FLOWED BACK 15 BBLS WELL DIED.
	9:30	11:30	2.00	WOR	16		Р		ND FRAC VALVE NU AND TESTED BOP.
	11:30	14:00	2.50	WOR	39		Р		RIH W/ 5 3/4 SOLID NO-GO, 2-JTS 2 7/8 L-80 EUE TBG, 5 3/4 PBGA, 2'-2 7/8 N-80 EUE TBG SUB, SN, 4'-2 7/8 N-80 EUE TBG SUB, 4-JTS 2 7/8 L-80 EUE TBG, 7" TAC, 262-JTS 2 7/8 L-80 EUE TBG. SET TAC @ 8574', SN @ 8709' AND EOT @ 8812'.
	14:00	16:00	2.00	WOR	16		Р		RD RIG FLOOR, ND BOP. NU WELL HEAD AND FLOWLINES, SHUT IN WELL. CLOSED ALL CSG AND TBG VALVES TO TREATER. TOO WINDY TO RD RIG. SDFN.
11/13/2015	10:00	11:30	1.50	MIRU	01		Р		ROAD RIG & EQUIP FROM THE 4-9C4 TO 3-31B4, MIRU COROD & EQUIPMENT
	11:30	13:30	2.00	INARTLT	06		Р		FLUSH TBG W/ 60 BBLS HOT 2% KCL, TBG FLOWING BACK, PUMP 20 BBLS BRINE WTR, STILL FLOWING BACK, PUMP 30 MORE BBLS BRINE, TBG WENT ON SLIGHT VACUUM.

**CENTRAL DIVISION** 

## 2.1 Operation Summary (Continued)

Date	Т	ime	Duratio	Phase	Activit	Sub	OP	MD from	Operation
	Sta	rt-End	n		у		Code	(ft)	
			(hr)						
	13:30	17:30	4.00	INARTLT	39		P		RIH W/ 2 1/2" X 1 3/4" X 38' HVF PUMP, 2' STAB SUB, ON/OFF
									TOOL, 5675' # 5 COROD, CUT # 5 COROD, POOH SPOOLING UP
									1153' # 5, WELD # 5 TO # 6 COROD, CLAMP OFF COROD,
									SECURE WELL, SDFD.
11/14/2015	6:00	7:00	1.00	INARTLT	28		Р		CREW TRAVEL HSM WRITE & REVIEW JSA ( TOPIC ) WELDING
									COROD
	7:00	9:30	2.50	INARTLT	03		Р		TBG TRYING TO FLOW, PUMPED 20 BBLS BRINE DOWN TBG,
									CONTINUE RIH W/ 1328' # 6 & 1300' # 7 COROD, TAG PSN,
									SPACE OUT COROD, CUT & WELD ON 1" PIN TO # 7 COROD, P/U
									2', 4', 6', 8' SUBS & POLISH ROD, SEAT PUMP
	9:30	10:00	0.50	INARTLT	18		Р		FILL TBG W/ 5 BBLS 2% KCL, STROKE TEST PUMP TO 1000 PSI,
									GOOD TEST, FLUSH FLOW LINE W/ 10 HOT BBLS
	10:00	11:30	1.50	RDMO	02		Р		RDMO COROD RIG, SLIDE ROTA FLEX AHEAD, HANG OFF
									COROD, START UNIT, TWOTO.

	STATE OF UTAH			FORM 9			
ı	DEPARTMENT OF NATURAL RESOU DIVISION OF OIL, GAS, AND M			5.LEASE DESIGNATION AND SERIAL NUMBER: Fee			
SUNDR	Y NOTICES AND REPORTS	SON	WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
	posals to drill new wells, significant reenter plugged wells, or to drill hori: n for such proposals.			7.UNIT or CA AGREEMENT NAME:			
1. TYPE OF WELL Oil Well				8. WELL NAME and NUMBER: Thorne 3-31B4			
2. NAME OF OPERATOR: EP ENERGY E&P COMPANY,	L.P.			9. API NUMBER: 43013520860000			
3. ADDRESS OF OPERATOR: 1001 Louisiana, Houston,	TX, 77002 713 997	NE NUMBER: Ext	9. FIELD and POOL or WILDCAT: ALTAMONT				
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0900 FSL 1400 FEL			COUNTY: DUCHESNE				
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 31 Township: 02.0S Range: 04.0W Me	U	STATE: UTAH				
11. CHECI	K APPROPRIATE BOXES TO INDIC	CATE NA	ATURE OF NOTICE, REPOR	RT, OR OTHER DATA			
TYPE OF SUBMISSION			TYPE OF ACTION				
	ACIDIZE	Па	LTER CASING	CASING REPAIR			
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	С	HANGE TUBING	CHANGE WELL NAME			
7,pp. Oximute date notice and control	CHANGE WELL STATUS	□ c	OMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE			
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	☐ FF	RACTURE TREAT	☐ NEW CONSTRUCTION			
1/25/2016	OPERATOR CHANGE	□ р	LUG AND ABANDON	PLUG BACK			
SPUD REPORT	PRODUCTION START OR RESUME		ECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION			
Date of Spud:	REPERFORATE CURRENT FORMATION		DETRACK TO REPAIR WELL	TEMPORARY ABANDON			
	TUBING REPAIR		ENT OR FLARE	WATER DISPOSAL			
DRILLING REPORT	WATER SHUTOFF		TA STATUS EXTENSION	APD EXTENSION			
Report Date:		si	TA STATUS EXTENSION				
	WILDCAT WELL DETERMINATION	<b>√</b> 0:	THER	OTHER: DO Plugs			
l .	COMPLETED OPERATIONS. Clearly sho 9840' & 9850'. See attache 8850'-9806' & 9869'-12-	ed for		Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY February 08, 2016			
NAME (PLEASE PRINT) Maria S. Gomez	<b>PHONE NUM</b> 713 997-5038	MBER	<b>TITLE</b> Principal Regulatory Analys	t			
SIGNATURE N/A			<b>DATE</b> 2/8/2016				

RECEIVED: Feb. 08, 2016

## **CENTRAL DIVISION**

ALTAMONT FIELD
THORNE 3-31B4
THORNE 3-31B4
RECOMPLETE LAND

# **Operation Summary Report**

Disclaimer: Although the information contained in this report is based on sound engineering practices, the copyright owner (s) does (do) not accept any responsibility whatsoever, in negligence or otherwise, for any loss or damage arising from the possession or use of the report whether in terms of correctness or otherwise. The application, therefore, by the user of this report or any part thereof, is solely at the user's own risk.

**CENTRAL DIVISION** 

#### 2.1 **Operation Summary (Continued)**

Date		ime rt-End	Duratio n	Phase	Activit y	Sub	OP Code	MD from (ft)	Operation
	13:30	17:30	(hr) 4.00	INARTLT	39		P		RIH W/ 2 1/2" X 1 3/4" X 38' HVF PUMP, 2' STAB SUB, ON/OFF TOOL, 5675' # 5 COROD, CUT # 5 COROD, POOH SPOOLING UP 1153' # 5, WELD # 5 TO # 6 COROD, CLAMP OFF COROD, SECURE WELL, SDFD.
11/14/2015	6:00	7:00	1.00	INARTLT	28		Р		CREW TRAVEL HSM WRITE & REVIEW JSA ( TOPIC ) WELDING COROD
	7:00	9:30	2.50	INARTLT	03		Р		TBG TRYING TO FLOW, PUMPED 20 BBLS BRINE DOWN TBG, CONTINUE RIH W/ 1328' # 6 & 1300' # 7 COROD, TAG PSN, SPACE OUT COROD, CUT & WELD ON 1" PIN TO # 7 COROD, P/U 2', 4', 6', 8' SUBS & POLISH ROD, SEAT PUMP
	9:30	10:00	0.50	INARTLT	18		Р		FILL TBG W/ 5 BBLS 2% KCL, STROKE TEST PUMP TO 1000 PSI, GOOD TEST, FLUSH FLOW LINE W/ 10 HOT BBLS
	10:00	11:30	1.50	RDMO	02		Р		RDMO COROD RIG, SLIDE ROTA FLEX AHEAD, HANG OFF COROD, START UNIT, TWOTO.
1/21/2016	7:30	10:30	3.00	MIRU	01		Р		ROAD COROD RIG FROM YARD TO 3-31B4, WRITE & REVIEW JSA ON SLICK SURFACES, HAD TO BLADE SNOW OFF LOCATION, SLIDE ROTA FLEX BACK, MIRU RIG & HOT OILER.
	10:30	12:30	2.00	PRDHEQ	14		Р		L/D POLISH ROD, WORK COROD JARRING ON PUMP, PUMPING HOT 2% KCL DOWN CSG, UNABLE TO UNSEAT PUMP, RELEASE OFF OF ON/OFF TOOL.
	12:30	15:00	2.50	PRDHEQ	39		Р		POOH W/ 1261' # 7, 1328' # 6, 4522' # 5, 1500' # 6 SE COROD & ON/OFF TOOL, SECURE WELL.
	15:00	16:00	1.00	RDMO	02		Р		RDMO COROD RIG & HOT OILER.
1/22/2016	6:00	7:30	1.50	MIRU	28		Р		CREW TRAVEL HELD SAFETY MEETING ON RIGGING UP RIG. FILLED OUT AND REVIEWED JSA.
	7:30	8:30	1.00	MIRU	01		Р		MIRU SERVICE RIG. WHILE PUMPING 80 BBLS DOWN CSG.
	8:30	10:30	2.00	WLWORK	21		Р		RU WIRELINE RIH PERFORATE TBG @ 8640' RD WIRELINE.
	10:30	12:30	2.00	WOR	16		Р		ND WELLHEAD, NU BOP. PRESSURE TEST BOP @ 5000 PSI HELD
	12:30	13:00	0.50	WOR	06		Р		FLUSHED TBG W/ 50 BBLS HOT 2% KCL.
	13:00	16:30	3.50	WOR	39		Р		TAC HANGING UP, TOOH W/ 262-JTS 2 7/8 L-80 EUE TBG, TAC, 4-JTS 2 7/8 L-80 EUE TBG. LD BHA.
	16:30	17:30	1.00	WOR	18		Р		CLOSED IN WELL. CLOSED AND LOCKED BLIND RAMS, CLOSED CSG VALVES AND INSTALLED NIGHT CAPS. RAN PUMP LINES AND SDFN.
1/23/2016	6:00	7:30	1.50	WOR	28		Р		CREW TRAVEL HELD SAFETY MEETING ON PICKING UP TUBING FILLED OUT AND REVIEWED JSA.
	7:30	12:00	4.50	WOR	39		Р		TALLIED AND RIH W/ 4 1/8" BIT, BIT SUB, 101 JTS 2 3/8 L-80 EUE TBG, X-OVER AND 202 JTS 2 7/8 TAGGED FILL @ 9804'. RU POWER SWIVEL.
	12:00	16:30	4.50	WOR	10		Р		PUMPED 400 BBLS @ 8 BPM ESTABLISHED REVERSE CIRCULATION. SLOWED RATE TO 5 BPM RETURNING 3 BPM WASHED DOWN TO CBP @ 9840' DRILLOUT CBPs 9840 AND 9850' CICRCULATE TBG CLEAN, CHASED REMAINS OF CBP TO 12463'. BTM PERF @ 12436'.
	16:30	17:30	1.00	WOR	39		Р		TOOH W/ 95-JTS 2 7/8 L-80 EUE TBG EOT @ 9405', CLOSED AND LOCKED PIPE RAMS, CLOSED TIW VALVE AND INSTALLED NIGHT CAP.CLOSED CSG VALVES AND INSTALLED NIGHT CAPS.
1/24/2016	6:00	7:30	1.50	WOR	28		Р		CREW TRAVEL HELD SAFETY MEETING ON TRIPPING TUBING. FILLED OUT AND REVIEWED JSA.
	7:30	10:30	3.00	WOR	39		Р		0 TSIP, 0 CSIP. TOOH W/ 201-JTS 2 7/8 L-80 EUE TBG, X-OVER, 101-JTS 2 3/8 L-80 EUE TBG, BIT SUB AND 4 1/8" BIT.

**CENTRAL DIVISION** 

#### 2.1 **Operation Summary (Continued)**

Date	Time Start-End		Duratio n (hr)	Phase	Activit y	Sub	OP Code	MD from (ft)	Operation
	10:30	13:30	3.00	WOR	39		Р		RIH W/ 2 3/8 BULL PLUG, 2-JTS 2 3/8 L-80 EUE TBG, 2'-2 3/8 N-80 TUBING SUB, DESANDER D-2305, 4'-2 3/8 TUBING SUB, 2 3/8 SN, 4-JTS 2 3/8 L-80 EUE TBG, 5" TAC, 59-JTS 2 3/8 L-80 EUE TBG, X-OVER AND 275-JTS 2 7/8 L-80 EUE TBG. SET TAC @ 10877'. SN @ 11008', EOT @ 11100'. LANDED TBG W/ 6' SUB AND TBG HANGER.
	13:30	14:30	1.00	WOR	16		Р		RD RIG FLOOR, ND BOP. REMOVED HANGER AND 6' SUB. LANDED TBG W/ 25,000 TENSION.NU WELLHEAD. OPENWELL TO TREATER.
	14:30	15:30	1.00	RDMO	02		Р		RD RIG AND SDFN.
1/25/2016	6:00	6:00	24.00	WOR	18		Р		NO ACTIVITY
1/26/2016	6:00	8:30	2.50	PRDHEQ	18		Р		CREW TRAVEL HELD SAFETY MEETING ON FLUSHING TUBING, FILLED OUT AND REVIEWED JSA. FLUSHED TBG W/ 55 BBLS KCL. 10 GALS CORROSION INHIBITOR. 5 BBLS KCL
	8:30	9:30	1.00	MIRU	01		Р		MIRU CO-ROD RIG.
	9:30	15:00	5.50	PRDHEQ	39		Р		RIH W/ 2" X 1 1/2" X 36' RHBC HVF ACCELERATED PUMP, RIH W/ PUMP, 1500' 16/16, 4522' 15/16, 1328' 16/16 AND 1261' 17/16. WELDED 0N 2275 18/16 WELDED TOP PIN. SPACED OUT W/ 1-8', 1-6', 1-4' 1-2' X 1" SUBS. FILLED TBG W/ 20 BBLS PRESSURE AND STROKE TEST @ 1000 PSI HELD.
	15:00	16:00	1.00	RDMO	02		Р		RD CO-ROD RIG. SLID IN PUMPING UNIT. PUT WELL ON PRODUCTION.